



This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

### Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

- + *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.
- + *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.
- + *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.
- + *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

### About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at <http://books.google.com/>

KF

HN 4R12 V

17117

HARVARD ENGINEERING SCHOOL

F

17

~~408.1~~  
~~80.2A~~  
~~9~~  
~~115~~  
~~22~~



HARVARD UNIVERSITY.

Bought  
with an appropriation made by  
the Corporation  
for books in Engineering.

Received *March 1, 1902.*





2/25







**WORKS OF**  
**PROFESSOR C. W. MACCORD**

PUBLISHED BY

**JOHN WILEY & SONS.**

---

**Descriptive Geometry.**

With Applications to Isometrical Drawing and Cavalier Projection. 8vo. vi + 248 pages, 280 figures. Cloth, \$3.00.

**Kinematics; or, Practical Mechanism.**

8vo. xi + 335 pages, 306 figures. Cloth, \$5.00.

**Mechanical Drawing.**

PART I. **Progressive Exercises.**

PART II. **Practical Hints for Draughtsmen.**

The two parts complete in one volume. 4to. 258 pages, 232 figures. Cloth, \$4.00.

**Velocity Diagrams.**

Their Construction and their Uses. Addressed to all those interested in Mechanical Movements. 8vo. iii + 116 pp., 83 figures. Cloth, \$1.50.

6

# VELOCITY DIAGRAMS.

THEIR CONSTRUCTION AND THEIR USES.

*INTENDED FOR ALL WHO ARE INTERESTED IN  
MECHANICAL MOVEMENTS.*

BY

CHARLES WILLIAM MACCORD, A.M., Sc.D.,

*Professor of Mechanical Drawing in the Stevens Institute of Technology,  
Hoboken, N. J.:*

*Formerly Chief Draughtsman for Capt. John Ericsson:*

*Author of "Kinematics," "Mechanical Drawing,"*

*"Elements of Descriptive Geometry," and*

*Numerous Monographs on Mechanism.*

*FIRST EDITION.*

FIRST THOUSAND.

NEW YORK:

JOHN WILEY & SONS.


LONDON: CHAPMAN & HALL, LIMITED.

1901.

~~170~~  
~~22~~

KF17117

~~408.1~~  
~~30.2A~~  
~~8~~



*Engineering Appropriation*

Copyright, 1901,  
BY  
CHARLES WILLIAM MACCORD.

ROBERT DRUMMOND, PRINTER, NEW YORK.

## PREFACE.

---

THIS treatise is in effect an abstract of a series of lectures forming a part of the course of instruction at the Stevens Institute of Technology. It explains the principles of the more common and convenient graphic processes of determining at any given instant the direction and velocity of the motion of a point, whether that motion be constant or variable.

It is intended not only for use in the classroom, but for the benefit of those who may wish to study the subject without the aid of an instructor.

C. W. MACCORD.

HOBOKEN, N. J., Oct. 12, 1901.



## VELOCITY DIAGRAMS.

---

1. It is a familiar fact that in the operation of any piece of mechanism, the parts go through a series of motions in regular order, finally returning to their original positions; after which the same series of motions is repeated, and so on indefinitely. One complete series is called a **cycle**; in completing which it frequently happens that, supposing the first or driving piece to move uniformly in one direction, the motions of other parts will vary either in velocity or direction, and often in both. And in studying the action of any mechanical movement, or in comparing the actions of different ones, it is often desirable to have a clear understanding of the law of variation, in regard to the motion of a given piece or a given point.

Now, assuming that for a given motion of the driver, the motion of the point considered can be determined at any instant, or in other words in any phase of the action—then it is beyond question that a graphic representation is the best if not indeed the only means of conveying to the mind a distinct and comprehensive idea of the law according to which the motion varies in velocity and direction.

Such a representation, or “**velocity diagram**,” is shown in Fig. 1. It consists merely of a curve whose abscissas, set

off from left to right upon the line  $MN$ , represent times, and the ordinates  $11'$ ,  $22'$ , etc., represent the velocities of the moving point at the instants indicated by the points 1, 2, etc.; the positive ordinates, or those above the line, indicate motion in one direction, that in the opposite direction being indicated by the negative ordinates, below the line. And a single glance at this figure is sufficient to establish the claim above made,—it gives in an instant all the information that could be gathered from lengthy explanations and tables of figures.




FIG. 1.

2. Now, given the velocity of the driver, how to determine the values of these ordinates? We have here to choose between two methods of procedure, the graphic and the analytic. There is no question that the members of a train of mechanism can be represented by symbols, the laws of their motions embodied in formulæ, and the desired values ascertained by algebraic computation. In the graphic method, the motion of a point at any instant is represented in magnitude and direction by a right line of definite length; and relations may be established between lines thus representing the motions of properly selected points, and other

lines closely connected with the moving pieces, such that the values sought can be determined by geometric reasoning. Of the two, the latter method is preferable for ordinary use, being far more simple and expeditious than the former, while the accuracy attainable is quite sufficient for practical purposes. Its foundations lie upon a few kinematic principles, of which we will briefly state the most important.

3. The first is the **composition** of motion. Suppose the point  $A$ , Fig. 2, to receive at the same instant two impulses, which separately would impart to it the motions represented in direction and velocity by the lines  $AB$ ,  $AC$ ; these are called **components**, and the **resultant** of these, which is the actual direction and velocity of the motion of the point, is




FIG. 2.

$AD$ , the diagonal of the parallelogram  $ABCD$ . The condition of things here is that  $A$  is a free point in space,—as if, by way of illustration, it were a billiard-ball impelled by the simultaneous strokes of two cues  $b$  and  $c$ , which are not connected with each other or with the ball; a consideration which, as will subsequently appear, is of no small importance. There may be more than two components; in that case, find the resultant of any two of them, compound that with any one of the others, and so on to the end. If there be three



components not in the same plane, these will be three adjacent edges of a parallelepipedon, and the resultant will be the body diagonal which passes through the moving point: our attention, however, will be chiefly confined to motions in one plane or, what is practically the same thing, in parallel planes.

4. The **resolution** of motion is the exact converse of the preceding. If a motion can be determined by compounding two others, that motion, if given, can be separated or *resolved* into its original components. Thus, in Fig. 2, suppose the motion  $AD$  to be assigned, and let it be required to determine two components having the directions  $Ax$ ,  $Ay$ , of which  $AD$  shall be the resultant. By drawing through  $D$  lines parallel to  $Ax$  and  $Ay$ , it is evident that we shall limit the required components,  $AC$ ,  $AB$ . But  $AD$  may be the diagonal of any one of an infinite number of parallelograms; whence it follows that a given motion may be resolved into two components respectively parallel to any two lines having different directions.

5. **Side Component and Longitudinal Component.**—In Fig. 3, let the point  $A$ , of the right line  $MA$ , have a motion represented by  $AD$ . Resolve this into the components  $AC$  perpendicular to  $MA$ , and  $AB$  in the direction of that line; then  $AC$  is called the side component, and  $AB$  the longitudinal component. And these components always exist, no matter how the motion  $AD$  may be resolved. Thus, if it be resolved into  $AC'$ ,  $AB'$ , then  $AC'$  itself has a component  $Ab$  along  $MA$ , and  $Ab$  is equal to  $B'B$ , so that the total longitudinal component is  $AB' + Ab = AB$ .

Again, in Fig. 4, let  $AD$  be resolved into  $AE$ ,  $AF$ ; then  $AE$  can be resolved into the rectangular components  $Ae$ ,  $Ag$ , and  $AF$  into the pair  $Af$ ,  $Ah$ ; also  $Af = eB$ , and

$Ah = Cg$ ;  $Ae$  and  $Af$  lie in the same direction, and the total longitudinal component is  $Af + Ae = AB$ ; but since  $Ag$  and  $Ah$  lie in opposite directions, the actual side component

FIG. 3.





FIG. 4.

is  $Ag - Ah = AC$  as before. These rectangular components  $AB$ ,  $AC$ , may properly be designated *absolute components*.

6. In Fig. 5, let  $AM$  represent a rigid and inextensible line—as a piece of stiff steel wire, and let the point  $A$  have a motion  $AD$ , of which  $AF$  and  $AE$  are the side and longitudinal components respectively. Then any other point,  $B$ , of this wire must of necessity have a longitudinal component  $BG$ , equal to  $AE$ , and in the same direction. And whatever the actual motion of the point, it follows from the preceding that the other component must be perpendicular to  $AM$ , so that the extremity of the resultant must lie in the

indefinite vertical line  $xx$  drawn through  $G$ . If, then, the direction  $By$  is assigned, the intersection  $H$  of  $xx$  and  $By$  will determine  $BH$ .




FIG. 5.

7. In Fig. 6,  $AM$ ,  $AN$ , represent two rigid bars, pivoted together at  $A$ ; let  $AE$ ,  $AF$ , be the absolute longitudinal components, from which it is required to find the motion of




FIG. 6.

$A$ . From what has just been shown, the extremity of the resultant must lie in  $Ex$  perpendicular to  $AM$ , and also in  $Fy$  perpendicular to  $AN$ ; it must, then, be their point of intersection  $D$ . Which is obviously as it should be, since the

resultant  $AD$  thus determined can be resolved either into the rectangular components  $AE, AG$ , or into the pair  $AF, AH$ . Had we proceeded as in Fig. 1, by completing the parallelogram of which  $AE, AF$  are the sides (as one not familiar with the previous reasoning would be very likely to do), the diagonal  $AK$  would have neither the right magnitude nor the right direction, unless  $AM$  and  $AN$  were perpendicular to each other: and, as will be seen subsequently, there are other cases than this in which that procedure will give erroneous results.

**8. Effect of Side Components.**—In Fig. 7, let  $MN$  be an inflexible steel rod, upon which the perforated balls  $A, B, C$ , are free to slide; then the centres of these balls are points *upon* the right line  $MN$ , but not *of* it, and, whatever their motions may be, the longitudinal components  $AH, BL, CR$  do not affect the line, nor do they have any relation to each other, and they need not have either the same magnitude or the same direction. But obviously the side components do affect the line,—if any two of them are equal, and lie on the same side of  $MN$ , the whole line must be translated bodily in the direction of those two, and the side components of all its points must be equal. But if motions be assigned to any two of these balls, such that their side components either lie upon opposite sides of  $MN$  or are unequal if they lie on the same side, then these two side components will establish a rotation of the line about some point of the line itself. If, for example, we give to  $A$  and  $B$  the motions  $AD$  and  $BE$ , their side components are  $AG$  and  $BK$  respectively, and, drawing  $GK$ , it is perceived that  $MN$  must turn about the point  $O$  where  $GK$  cuts it. Moreover, this latter line determines the directions and the values of the side components of the motions of all other points on  $MN$ ; thus any point  $C$ ,

to the left of  $O$ , must move upward, and that at a rate  $CP$  limited by the prolongation of  $GK$ ; any point to the right of  $O$  must move downward in like manner, while if a ball were placed at  $O$ , it could not move sidewise at all, though it

FIG. 7.





FIG. 8.

might move endwise in either direction and with any velocity.

9. Now if, as in Fig. 8, we consider  $A, B, C$ , to be points of the inflexible and inextensible line  $MN$ , and therefore as remaining always at fixed distances from each other; it is still true that the side components  $AG, BK$ , of the simultaneous motions of two points,  $A$  and  $B$ , for example, determine the rotation of  $MN$  about  $O$ . But supposing  $AD$  to be assigned, the motion of  $B$ , for instance, would no longer be entirely arbitrary, since the longitudinal component  $BL$

must be equal to  $AH$  and in the same direction. This is also true of every point of  $MN$ , including  $O$ , whose absolute motion must therefore be  $OQ, = AH$ . Consequently in this case, since  $GD, OQ, KE, PF$ , are all equal, and all parallel to  $MN$ , the line  $DQEF$ , joining the extremities of the resultants, will be equal and parallel to  $GOKP$ , joining the extremities of the side components.

**10. Representation of Angular Velocity.**—The linear velocity of a point at unit distance from a centre about which the point travels in a circular arc, is the measure of the *angular velocity* of the point about that centre. From which it follows, that whatever the distance of the point from the centre, we shall always have the value, angular velocity  $= \frac{\text{linear velocity}}{\text{radius}}$ .

If then, as in Fig. 9 the point  $A$ , revolving about the




FIG. 9.

centre  $C$ , has the linear velocity  $AK$ , the angle  $ACK$  represents the angular velocity; if it be desired to find the linear velocity of  $B$  in rotating with the same angular velocity about  $D$ , we have only to make the angle  $BDL$  equal to  $ACK$ . If the angular velocity of  $B$  is to be made twice that of  $A$ , however, it is to be noted that this is not done by

doubling this angle; but we make  $AM = 2AK$ , and then make the angle  $BDN = \text{angle } ACM$ .

**11. The Instantaneous Axis of Rotation.**—In Fig. 10, let  $AB$  represent an inflexible and inextensible rod, and first let the points  $A$  and  $B$  move in the plane of the paper, in opposite directions perpendicular to  $AB$ , with velocities  $AF$ ,  $BK$ : these motions establish a rotation of the rod about the point  $I$ , determined by drawing  $FK$ . If we now add a longi-




FIG. 10.

tudinal component to the motion of each point, as  $AE = IG = BC$ , the resultant motions of  $A$  and  $B$  will become  $AD$  and  $BH$ , and that of  $I$  will be  $IG$ .

Draw, through  $A$  and  $I$ , lines perpendicular to  $AD$  and  $IG$  respectively, intersecting in  $O$ ; draw also  $DO$  and  $GO$ . Then the triangles  $AFD$ ,  $AIO$ , are similar, whence

$$\frac{AF}{AI} = \frac{AD}{AO} = \frac{FD}{OI} = \frac{IG}{IO}$$

Therefore the angles  $AOD$ ,  $GOI$ , are equal; that is to say, the two points  $A$  and  $I$  are rotating with the same angular velocity and in the same direction about the centre  $O$ . The same must therefore be true of every other point of the rigid bar. This may be at once verified as to the point  $B$ , as follows; we have already shown that  $\frac{AD}{AO} = \frac{AF}{AI}$ ; therefore the angles  $AOD$ ,  $AIF$ ,  $BIK$ , are equal, whence

$$\frac{AF}{AI} = \frac{BK}{BI} = \frac{IG}{OI} = \frac{KH}{OI}.$$

Therefore the triangles  $BKH$ ,  $BIO$ , are similar, and  $BH$  is perpendicular to  $BO$ .

With reference to the bar  $AB$ , the point  $O$  is called the **instantaneous axis**, because during the motion of the bar, it changes its position from instant to instant, not only in space but relatively to the bar itself; and it is found, when the simultaneous motions of two points of the bar are given, as for example  $AD$ ,  $BH$ , by drawing through each point a line perpendicular to the direction of its motion; the intersection of these perpendiculars locates the axis sought.

And obviously, since the bar is rigid, any point rigidly connected with it must obey the same law, and rotate about the instantaneous axis with the same angular velocity and in the same direction.

**12. The Instantaneous Centre.**—The rotation about  $O$ , then, is equivalent to a rotation about  $I$ , in the same direction and with the same angular velocity, combined with a longitudinal motion.

As a distinctive name, then, this point  $I$  may properly be called the **instantaneous centre**.





way, and compel it to turn, in this case in the opposite direction. Draw the contact radii  $PC$  and  $PD$ ; also draw through  $P$ ,  $TT$  the common tangent to the two curves, and  $NN$  their common normal. The point  $P$  of the driver must move in a direction perpendicular to  $PD$ ; let its linear velocity be represented by  $PA$ , which can be resolved into the normal component  $PE$  and the tangential component  $PF$ . Of these two, the latter is obviously non-effective; it represents merely the sliding of  $P$  along the tangent, and has no tendency to move the follower. The motion of the point  $P$  of the right-hand piece must be perpendicular to  $PC$ , and must have a velocity such that its normal component shall also be  $PE$ ;—consequently the extremity  $B$  of this resultant must lie in the line  $AE$ . The component  $PH$  also represents sliding along the tangent; it is clear, therefore, that in this case the actual sliding of one piece upon the other will be  $PF - PH$ , or  $HF$ .

**14. Roberval's Method of Drawing Tangents.**—Whatever the path described by a moving point, the direction of its motion at any instant is that of the tangent to that path, at the position occupied by the point at the given instant.

The law of the motion, even in abstract mathematics, may often be best explained by describing it as dependent upon, and produced by, other motions: thus, for example, a spiral of any kind is usually defined as the path of a point which travels along a right line, while the line itself revolves about a fixed centre.

And "**Roberval's method**" of drawing a tangent to a curve consists simply in finding the resultant of these component motions. A simple illustration of this method is shown in its application to the spiral of Archimedes, Fig. 12. Let a point move at a uniform rate from  $P$  along the right line  $PQ$ ,

while that line revolves in the direction of the arrow around  $P$  as a fixed centre, also at a uniform rate. Let the radial travel be such that, while making one revolution, the point shall move from  $P$  to  $A$ , then it will trace the curve  $PEFAG$ ; and let it be required to draw a tangent at the point  $O$ . The two motions might be supposed to take place independently; if we first imagine the rotation to be arrested, the




FIG. 12

point will move, in the time of one revolution, radially outward through a distance  $ON$  equal to  $PA$ : and we may therefore let  $ON$  represent the velocity of this component. If we suppose the radial motion to be arrested, then in the same time the point will describe the circumference of the circle of which  $PO$  is the radius. The direction of this motion at the instant being that of the tangent to the circular path, we have as the other component  $OM$  perpendicular to  $PO$ , and equal in length to the circumference; then, completing the rectangle, the diagonal  $OR$  is tangent at  $O$  to the spiral, as required: obviously, both components may be reduced in the same proportion, without affecting the direction of the resultant, which is of course independent of the actual velocity of the tracing point.

Since  $\frac{NR}{ON} = \tan. NOR$ , the inclination of the tangent to the radius vector can be determined by elementary trigonometry; and in its application to many other curves, of high and low degree, a like simplicity characterizes this elegant process. Nevertheless, in his treatise on Descriptive Geometry, Mr. J. F. Heather makes this curious remark: "This method, which Roberval invented before Descartes had applied algebra to geometry, is implicitly comprehended in the processes of the differential calculus, on which account it is not noticed in elementary mathematics";—where it would seem, on the contrary, to deserve a conspicuous place: it is certainly more easily comprehended than the calculus, to which indeed it is a natural prelude. At any rate, it has a natural and direct application to our present purpose, since in mechanical devices the actual motion of a point is, more often than not, controlled by other motions whose combined effect it is necessary to determine.

15. But in applying it, all the circumstances of the case must be considered, and all the conditions which may affect the result must be satisfied. This suggestion may at first glance appear superfluous; but it seems otherwise in view of the fact that Mr. Heather, in the only illustration of Roberval's method which he gives, has conspicuously failed to act upon it. The curve selected for this solitary example is the ellipse, traced, as in Fig. 13, by a point  $P$  moving in such a manner as to keep always taut a thread  $APB$  attached by its extremities to the foci  $A$  and  $B$ .

Mr. Heather's explanation is as follows: "Since the length of the string is constant, the distance  $AP$  is lengthened at each instant of the motion by the same distance as the distance  $BP$  is diminished. The velocity of the describing

point in the direction  $AP$  is therefore equal to the velocity in the direction  $PB$ . If, then, equal straight lines be cut off from  $PB$ , and from  $AP$  produced, and the parallelogram  $PNOM$  be completed, the diagonal  $PO$  of this parallelogram will be the direction of the motion of the generating point at  $P$ , and consequently the tangent to the curve at this




FIG. 13.

point. It is clearly seen from this, that in the ellipse, the tangent bisects the angle  $BPV$  formed by one of the focal distances and the production of the other," etc., etc.

Mr. Heather elsewhere explicitly states that if the components in two directions are given, whatever their relative magnitudes, the method of Roberval consists in "completing the parallelogram and drawing the diagonal." In the above example the *direction* of the tangent is, undeniably, correctly found in this manner—and the same is true if this construction is applied to the hyperbola, in which the moving point recedes from both foci at the same rate, or to the

parabola, in which it recedes at the same rate from the focus and the directrix.

16. In all these cases, however, the components are *equal*; but the statement above quoted leads us to expect a correct determination whether they are equal or not: let us put it to the test. In Fig. 14, let  $A$  and  $B$  be two fixed points, with reference to which the point  $P$  moves subject to the condition that  $PB$  shall always be twice  $PA$ . In other words, the path of  $P$  is the locus of the vertices of all triangles of which  $AB$  is the common base, and one of the two other sides is twice the third. In order to preserve this ratio it is clear that  $P$ , in moving to the right, must recede




FIG. 14.

from  $B$  twice as fast as it does from  $A$ . Consequently, setting off on the prolongations of  $BP$  and  $AP$ ,  $PM = 2PN$ , and completing the parallelogram, the diagonal  $PO$  should, in accordance with what immediately precedes, be the required tangent. But it can be shown that the path in question is the circumference of the circle whose diameter is  $DE$ , determined by making  $BD = 2AD$ , and  $BE = 2AE$ . It is

obvious that  $PO$  is *not* tangent to this circle, and therefore cannot be the resultant motion of  $P$ .

A little reflection will show that two important conditions have been neglected ; the point  $P$  lies upon the right line  $PA$ , and must always do so ; therefore, if that point moves as shown, the line must turn about  $A$  as a fixed centre ; and similar reasoning applies to the line  $PB$ . Thus the situation is in fact more complicated than it seemed at first, and really presents a special case of the general problem of determining the motion of the intersection of two right lines rotating about fixed centres ; which therefore must next receive attention. The elements of this problem are embodied in the mechanical combination shown in Fig. 15, where  $AC, BD$ , represent two steel rods, each formed into an eye at one end and turning about the fixed pins  $C, D$  ; upon these rods two sleeves slide freely, and they are pivoted together by a pin at  $P$ , whose axis, perpendicular to the paper, intersects the centre lines of both rods.

The operation of this device may perhaps be best studied by first supposing one rod, as  $AC$ , to be held stationary, while  $BD$  turns. The point  $P$  of that rod must then at the instant move in a direction perpendicular to  $BD$  ; let its velocity be represented by  $PG$ . The pin connecting the sleeves must move absolutely in the direction  $PC$ , since the rod  $AC$  now forms a fixed guide, along which the sleeve through which it passes is compelled to slide. The other sleeve, however, not only rotates with  $BD$ , but can slide along that rod : consequently the actual velocity  $PI$  of the pin  $P$  is found by drawing through  $G$  a parallel to  $BD$ . Drawing  $IH$  parallel to  $PG$ , we observe that upon the supposition above made the pin  $P$  moves in the direction  $AC$  at the rate  $PI$ , and in the direction  $BD$  at the rate  $PH$ .

Next let  $BD$  be held stationary, and let the point  $P$  of the rod  $AC$  move in rotation about  $C$  with the velocity  $PL$ . By similar reasoning we shall find the resultant motion of the pin  $P$  to be  $PF$  in the direction  $BD$ , and it will be accompanied by a motion  $PE$  in the direction  $AC$ .




FIG. 15.




FIG. 16.

17. Now if both rods rotate at once, with the same velocities as before, the final resultant motion  $PR$  of the pin  $P$  is found by considering the partial resultants  $PI$ ,  $PF$ , as components, and completing the parallelogram; because, as we have just seen, these are wholly independent of each other. But it is to be noted that  $P$  will move toward  $C$  with a velocity equal to  $PI + PE$ , and toward  $D$  with a velocity equal to  $PF + PH$ . Drawing  $RM$  perpendicular to  $BD$ , and  $RN$  perpendicular to  $AC$ , we have  $FM = PH$ , and  $IN = PE$ : so that  $PM$ ,  $PN$ , are the velocities of  $P$  in the directions  $BD$ ,  $AC$ , respectively.

Also, since  $FR$ ,  $IR$ , are merely prolongations of  $LF$  and  $GI$ , it will be seen that having assigned the components of



rotation,  $PG$  and  $PL$ , the resultant  $PR$  may be at once determined by drawing perpendiculars to them, which will intersect in  $R$ ; then drawing  $RM$  and  $RN$ , we determine  $PM$  and  $PN$ , the total sliding components.

If then, as in Fig. 16, the components  $PN$ ,  $PM$ , are assigned, the resultant is found, not by completing the parallelogram, but by drawing  $Nz$ ,  $Mw$ , respectively, perpendicular to  $AC$  and  $BD$ ; these intersect in  $R$ , and  $PR$  is the resultant. Had this resultant been assigned, the sliding components are found at once as above stated, by reversing this process; and the components of rotation are determined as readily by drawing  $Px$  perpendicular to  $AC$ , and  $Py$  perpendicular to  $BD$ , upon which lines we let fall from  $R$  the perpendiculars  $RL$ ,  $RG$ .

18. This, then, is the proceeding which should have been adopted in Figs. 13 and 14. Applying it in those cases, we find the resultant motion of the point  $P$  upon the ellipse to be  $PR$  instead of  $PO$ ; the direction is the same, but the magnitude is different, and plainly will be so except in the case when  $PA$  and  $PB$  are perpendicular to each other: in Fig. 13, when the angle  $APB$  is obtuse, as shown at the right,  $PO$  is too great; and when  $APB$  is acute, as shown at the left,  $PO$  is too small. And in Fig. 14 it is seen that the direction as well as the magnitude of the true resultant  $PR$  is widely different from that of  $PO$ ; moreover, it can be proved that  $PR$  is in this case perpendicular to the radius  $PC$ , and therefore tangent, as it should be, to the circular path  $DPE$ .

The manner of determining the resultant, when the components  $PM$ ,  $PN$ , Fig. 16, are assigned, is in this case precisely the same as that employed in Fig. 6. But the conditions are by no means the same; in that instance the lines

along which the given components lie intersect always in the same point *A*, whereas in this the point of intersection moves along both lines; and they both clearly illustrate the fact that Roberval's method does not always consist in merely completing the parallelogram of two given components and drawing the diagonal.

19. The problem under consideration has thus far been limited by supposing the fixed centres of rotation to lie upon the lines themselves. It is clearly not essential that this should be so,—one or both these centres may be otherwise located; and the latter case is illustrated in Fig. 17, where the rigid rods *AS*, *BT*, are riveted into, and form




FIG. 17.




FIG. 18.

parts of, the arms *CS*, *TD*. Suppose, as before, one piece, as *ASC*, to be held stationary, and let the other move, the point *P* of the latter having the velocity *PG*; the direction of this motion is, of course, perpendicular, not to *BT*, but to *PD*. The resultant motion of the pin connecting the sleeves must, as before, be in the direction *PS*; and in order to produce it there must be compounded with *PG*, the component of rotation, a sliding component in the direction *BT*:

because by the structure of the mechanism these are the only motions of which the sleeve upon the rod  $BT$  is capable. Therefore, the first partial resultant  $PI$  is found by drawing through  $G$  a parallel to  $BT$ ; and the sliding along  $BT$ , by drawing through  $I$  a parallel to  $PG$ —which is perpendicular to  $PD$ .

Next, keeping  $BT$  stationary, assign to the point  $P$  of the other rod a rotative component  $PL$ , perpendicular to  $PC$ ; then by similar reasoning we find the other partial resultant  $PF$ , and sliding component  $PE$ . Compounding these two partial resultants as in Fig. 15, we obtain the final resultant  $PR$ , as the motion of the pin  $P$  when both rods move with the assigned velocities;—and the total rate of sliding along each rod is found by drawing  $RN$  perpendicular to  $PC$ , and  $RM$  perpendicular to  $PD$ .

20. We are now in a position to make the problem still more general, and to determine the motion of the point of intersection of two *curved* lines rotating about fixed centres. In Fig. 18, the rigid steel rods  $JK$ ,  $QO$ , bent into the forms of circular arcs, pass through correspondingly curved sleeves pivoted together at  $P$ , and, being riveted into the arms  $JD$ ,  $QC$ , are compelled to rotate about the fixed centres  $D$ ,  $C$ . Through  $P$  draw a tangent to each curve; for facility of comparison, this combination has been purposely so drawn that these tangents are parallel to  $BT$ ,  $AS$ , of Fig. 17, and that the points  $P$ ,  $C$ , and  $D$ , have the same relative positions as in that diagram.

Proceeding as before, we assign a rotative component  $PG$  to the point  $P$ , on the arc  $JK$ , the right-hand piece being held stationary. Then it will be at once seen that the first partial resultant  $PI$  must have the direction of the tangent  $PS$ , while the sliding component must have the di-

rection  $PT$ , tangent to  $JK$ . Further explanation is needless, it being now quite apparent that the final resultant  $PR$ , and the total rate of sliding,  $PM$  and  $PN$ , are determined precisely as in Fig. 17.

21. Going one step farther, it is to be observed that the circular arcs  $JK$ ,  $OQ$ , might be tangent at  $P$  to any two curves whatever, circular or otherwise; and supposing those curves to rotate about  $C$  and  $D$ , the motion of  $P$  at the instant would not be in any way affected by the substitution. It is true that if the new curves are non-circular, the device of the sliding sleeves can not be employed. But by this time it should have been perceived that they are not at all necessary any case, and that the motion of the point of intersection of the two lines, straight or curved, is in fact determined by the rotations alone.

Nevertheless, these sleeves have, as we think, been of service in the investigation, by making apparent to the eye the reasons for certain steps in the process of finding the resultant sought. And though just such combinations as these may not be met with in mechanism, yet very similar ones may be, and at any rate it has already been shown that the main question has an important bearing on some mathematical problems; nor need we go far to find instances in which its solution may be of direct practical interest.

22. For example, given the velocities of the blades of a common pair of shears, what is the rate of *shearing cut*? The same question may be asked in relation to the pruning scissors with curved blades, shown in Fig. 19. Here  $C$  is the common centre of rotation,  $AS$  is tangent to the upper blade, and  $BT$  to the lower one, at their intersection  $P$ . Regarding  $C$  as fixed, let  $PG$ ,  $PL$ , be the components of rotation, both of which are perpendicular to  $PC$ . Draw

through  $G$  a parallel to  $BT$ , and through  $L$  a parallel to  $AS$ ; these intersect in  $R$ , and  $PR$  is the motion of the point of intersection. This will be readily seen by the aid of the reference letters to be a case precisely similar to that shown in Fig. 18; when the blades are straight, as in the common shears, each edge is its own tangent, and the construction is made as in Fig. 17.




FIG. 19.

**23.** The direction and velocity of the motion of a point may also be determined in many cases by means of the instantaneous axis. For example: In Fig. 20,  $C$  and  $D$  are the fixed centres upon which turn the levers  $CA, DB$ ; the points  $A$  and  $B$  are connected by the link  $AB$ , which is extended in a curved form to  $P$ : the motion of  $A$  is necessarily perpendicular to  $CA$ , and letting  $AM$  represent its velocity, it is required to find the velocity of the points  $B$  and  $P$ . Since  $B$  is constrained to move in a direction perpendicular to  $DB$ , the instantaneous axis is found by producing  $CA, DB$ , until they intersect in  $O$ ; then drawing  $OM$ , the angle represents

the angular velocity of  $A$  around  $O$ ; and this must be the same for every point of the rigid piece  $ABP$ . Also, the direction of the motion of every such point must be perpendicular to the *instantaneous radius*, or line drawn from the point in question to the instantaneous axis. Therefore, drawing through  $B$  a perpendicular to  $BO$ , and through  $P$  a perpendicular to  $PO$ , the required velocities  $BN$ ,  $PR$ , are determined by making the angles  $\delta'$ ,  $\delta''$ , each equal to  $\delta$ , or  $AOM$ .

In the present instance this affords, perhaps, the most




FIG. 20.

simple means of determining the motion of  $P$ ; and since the direction of this motion must be tangent to the path of that point, attention is thus drawn to the fact that by the use of the instantaneous axis, a tangent to a curve may sometimes be drawn even more readily than by Roberval's method.

**24.** But the circumstances may be such that the instantaneous axis is inaccessible, or that its determination is un-

reliable; one or both of which things would have resulted if, in Fig. 20, the two levers had been nearly parallel. In this event other means must be employed, and in Fig. 21 a different process is illustrated, the conditions, for facility of comparison, being the same as in the preceding figure. The assigned motion  $AM$  has an absolute component  $Ae$  in the direction  $AB$ , and the motion of  $B$  must have an equal component  $Be'$  in the same direction. The actual motion of  $B$  must be perpendicular to  $BD$ , and its velocity  $BN$  is determined by drawing through  $e'$  a perpendicular to  $Ae'$ . Draw  $BP$ ; then  $BN$  will have an absolute component  $Bg$  in this direction, to which  $Pg'$  must be equal. Also draw  $AP$ ;




FIG. 21.

then  $AM$  has an absolute component  $Af$  in that direction, to which  $Pf'$  is equal. Through  $g'$  draw a perpendicular to  $Bg'$ , and through  $f'$  a perpendicular to  $Af'$ ; these intersect in  $R$ , and  $PR$  is the required motion of the point  $P$ .

**25. Composition of Revolution and Rotation.**—Numerous mechanical devices are practically employed, in which one wheel not only rotates about its own axis, but at the same

time travels in an orbit about another fixed axis, thus constituting what is called a planetary train. Any point connected with the planetary wheel then travels in a path dependent upon both these circular motions, and consequently called an *aggregate* path. The general principle is illustrated in Fig. 22; the wheel  $W$ , whose centre is  $C$ , has its bearings in the train-arm  $AD$ , which turns about  $D$  as a fixed centre; and this wheel may be made to turn in its bearings, independently of the motion of the arm, by any suitable means. Supposing the arm to be stationary, let the wheel rotate as shown by the arrow  $x$ , with such a rate that a pin  $P$  fixed in the side of  $W$  shall move with a velocity  $PQ$ , the direction of this motion being necessarily perpendicular to  $PC$ .

Next, suppose  $W$  not to turn at all about  $C$ , and let the train-arm move as shown by the arrow  $y$ , the velocity of  $A$




FIG. 22.

being represented by  $AM$ , perpendicular to  $AD$ . Since the arm and the wheel now move as one piece, this will impart to  $P$  a motion perpendicular to  $PD$ , the velocity  $PN$  being



determined by making the angle  $\delta'$  equal to the angle  $\delta$ . Now, if these two movements take place simultaneously, the resultant motion of  $P$  will be determined by compounding  $PQ$  and  $PN$ ,—that is, by completing the parallelogram and drawing the diagonal  $PR$ ; because the rotation about  $C$  and the revolution about  $D$  are wholly independent of each other, both in direction and in velocity.

26. Before proceeding to the construction of a complete velocity diagram, we propose to give a series of examples showing how the principles and processes above described may be combined and applied in determining the motions of certain points in detached mechanical movements. It is immaterial whether the combinations selected are, or are not, parts of actual machines, because it would be difficult to contrive a "mechanical movement" of practical form which might not some time be found adaptable to a useful purpose. And the study, or better still, the actual execution, of such exercises, in which attention is confined to the action of comparatively few parts, will be found the best means of acquiring thorough familiarity with the principles, and facility in their application.

27. In the first of these examples, Fig. 23, the lever  $CP$  is pivoted at  $C$  to a socket which slides along the fixed guide  $TT$ , and at  $A$  the link  $AQ$  is joined to this lever. Let  $AL$  be the absolute component of the motion of  $A$ , in the line of this link, and let  $CM$  be the resultant motion of  $C$  along the guide; it is required to find the actual motions of the points  $A$  and  $P$ . Resolve  $CM$  into the components  $CD$  in the direction  $PC$ , and  $CE$  perpendicular to it; then  $PH$ ,  $AF$ , will be the absolute components of the motions of  $P$  and  $A$  in the line of the lever, each being equal to  $CD$ . Draw through  $L$  a perpendicular to  $AQ$ , and through  $F$  a perpendicular to




FIG. 23.

$PC$ ; these intersect in  $N$ , and  $AN$  is the required resultant motion of  $A$ . The side component of  $AN$  is  $AG$ ; and the two side components  $AG, CE$ , determine a rotation of  $PC$  about the point  $I$ , where it intersects the prolongation of  $GE$ . The prolongation of  $EG$  limits  $PK$ , the side component of the motion of  $P$ , which, compounded with  $PH$ , determines  $PR$ , the required resultant.

One test of the accuracy of the construction is to draw the line  $RNM$  through the extremities of the resultants; this should be parallel to  $KGE$ , and when produced to cut the prolongation of  $PC$  in  $B$ ,  $IB$  should be equal to  $CD$ .

Another test is to find the instantaneous axis of  $CP$ , by drawing, through  $P$  and  $C$ , lines perpendicular to  $PR$  and  $CM$  respectively. These intersect in  $O$ : and not only should all the angles marked  $\delta$  be equal to each other, but  $OI$  should be perpendicular to  $PI$ , and  $OB$  perpendicular to  $RB$ .

28. In Fig. 24, a lever turning about the fixed centre  $D$




FIG. 24.

is jointed at  $P$  to a rod  $PR$ , which slides freely through a sleeve formed in the outer end of a rigid arm  $EC$ , which

turns about the fixed centre  $C$ . Given the motion  $PA$  of the point  $P$ , it is required to find the motions of  $R$  and of the point  $E$  of the arm  $EC$ , and also the rate of sliding of the rod through the sleeve.

The only motions of which the rod  $PR$  is capable, are those of revolving around the centre  $C$ , and of sliding end-wise through the sleeve. We may, then, resolve  $PA$  into the sliding component  $PV$  in the line of the rod, and the rotative component  $PM$  perpendicular to  $PC$ . The former gives at once the rate of sliding, and the latter determines the angle  $PCM$ , or  $\beta$ , which represents the angular velocity of the rotation about  $C$ ; this is the only motion of which the curved arm is capable, and  $EF$ , the required motion of the point  $E$  on that arm, is perpendicular to  $EC$ , and limited by making the angle  $ECF$  equal to  $\beta$ . The motion of  $R$  has also a rotative component  $RH$ , determined in like manner, and also a longitudinal component  $RG, = PV$ ; completing the parallelogram,  $RB$  is the resultant sought.

Otherwise, the instantaneous axis of the rod  $PR$  might have been found thus: draw  $CI$  perpendicular to  $PR$ , then, in rotation about  $C$ , the motion of the point  $I$  would be perpendicular to  $CI$ , and therefore longitudinal in respect to the rod. This must be true also in the rotation about the instantaneous axis of the foot of the perpendicular from that point upon the rod; consequently, that foot can be no other than the point  $I$ , and the instantaneous axis  $O$  may thus be found by producing  $CI$  to cut the prolongation of  $DP$ . Then drawing  $AO$  and  $OR$  we may determine the absolute motions of  $R$  and of  $I$  by making the angles marked  $\delta$  equal to each other.

A test of this may be applied by resolving  $PA$  into the components  $PQ$  along the rod, and  $PS$  perpendicular

to it; resolve  $RB$  in a similar manner, then  $PQ$ ,  $IW$ , and  $RU$ , should be equal to each other, and  $ST$  should pass through  $I$ .

The point  $E$  of the rod must have an absolute component  $EV = PQ$ ; this does not indicate the whole sliding, since  $EF$ , the motion of  $E$  on the arm, has a sliding component  $EJ$  in the opposite direction; the sum of these, or  $JV$ , is equal to  $PN$ , which was previously determined by another method.

**29.** In Fig. 25,  $D$  is the fixed centre about which turns the lever  $DB$ , jointed at  $B$  to the bar  $ABP$ . The motion of  $A$  is constrained by the lever  $AC$ , which turns about  $C$  as a fixed centre. Given the motion  $BM$ , it is required to find the motion of  $P$ .

This may be done in three different ways.

*First.* Resolve  $BM$  into the rectangular components  $BE$ ,  $BF$ , then  $AF'$ ,  $PF''$ , must be equal to  $BF$  and in the same direction. The motion of  $A$  must be perpendicular to  $AC$ , is limited by  $F'N$  perpendicular to  $AB$ , and has the side component  $AE'$ . A line through  $E'$  and  $E$  limits the side component  $PE''$ , and  $PR$  is found by compounding  $PE''$  with  $PF''$ .

*Second.* (Same Figure.) Produce  $CA$  to cut  $BD$  in  $O$ , the instantaneous axis of  $AP$ ; draw  $MO$  and  $PO$ , also  $Px$  perpendicular to  $PO$ . Construct the angle  $POy$  equal to the angle  $BOM$ ;  $Px$  cuts  $Oy$  in  $R$ , and  $PR$  is the resultant sought.

*Third.* In Fig. 26, find  $BF$ ,  $AN$ , and  $AE'$ , as in the first solution. Now, the motion of  $P$  may be regarded as compounded of a rotation around  $B$  and a revolution around  $D$ . The former component is  $PG$  perpendicular to  $ABP$ , limited by the prolongation of  $E'B$ ; the latter is  $PH$  perpendicular to  $PD$ , determined by making the angle  $PDH$  equal to the angle  $BDM$ . Completing the parallelogram, the diagonal  $PR$  is the required resultant.




FIG. 25.




FIG. 26.

Either of these processes may be used as a check upon the other—and in practice it is often advisable to apply such tests, which may lead to the detection of an error; or, what is still more satisfactory, prove that none has been made.

**30. Of Rolling Contact.**—There are numerous mechanical devices in practical use, in which the motions of certain parts are determined by their connection with a curve which *rolls* upon another line which is itself stationary, and may be either curved or straight.

The nature of perfect rolling contact may perhaps be best illustrated by a study of that which is not perfect. Thus, in Fig. 27, the polygon rolls upon the fixed right line with a hobbling motion; in the position shown, the point *A* is at rest, and the whole figure turns about it as a centre until *B* comes into *LM* at *D*; it will then turn about *B* until the face *BE* coincides with *LM*, and so on: the perimeter of the polygon “measuring itself off” upon the straight line along which it rolls.

If the number of sides be increased, their length will be less, and the hobbling will be diminished, until, when the number becomes inconceivable, it will become imperceptible. The broken contour then becomes the dotted curve, tangent to the base line upon which it rolls, and the change from one centre of rotation to another goes on continuously. But this does not alter the facts, that at any instant the point of contact is *at rest*, and that every point of the curve, as well as every point rigidly connected with it, is at the instant turning about that point of contact as a fixed centre.

In this case the polygon, being a regular one, ultimately becomes a circle; and when it does, the path of its centre is a right line parallel to *LM*. And it will now be apparent that the *rolling* of this circle upon its tangent is the resultant

of a rectilinear translation indicated by the arrow  $t$ , and a rotation about the centre  $C$  of the circle indicated by the arrow  $r$ . On  $LM$  set off  $AN$  equal to the quarter circumference  $ABE$ , and erect the perpendicular  $NC'$ ; then if the circle, without rotating, be moved bodily to the right until  $C$  reaches  $C'$ , the single point  $A$  of the circle will have been brought into contact with every point of  $AN$ ,—and this is pure *sliding* contact. On the other hand, we may suppose  $C$  to remain fixed, and the circle to turn as shown by the arrow  $r$  through the angle  $ECA$ , or  $90^\circ$ ; then every point of the quadrant  $ABE$  will have been brought into contact with the single point  $A$  of the tangent,—and this also is pure sliding contact.

31. But if these two motions take place simultaneously and uniformly, it is obvious that the circumference will measure itself off upon the tangent, the point 1 on the arc going to 1' on the tangent, 2 going to 2', and  $E$  going to  $N$ . The consecutive points of the arc, then, come into coincidence with the consecutive points of the line, each in their order of sequence; and this is pure *rolling* contact; no point of either comes in contact with more than one point of the other, and the length of the line rolled over is precisely equal to the length of the arc which rolls over it. Moreover, it is clear that the motions of the point  $A$ , due to the rotation  $r$  and the translation  $t$ , respectively, are opposite in direction and equal in velocity; they therefore neutralize each other, leaving the point of contact for the instant stationary, as previously stated.

Now, in Fig. 28, the base line  $LM$ , instead of being straight, is a part of a circle whose centre is  $D$ . Set off the arc  $AN$  equal to the quadrant  $AE$ ; then if the point  $A$  of the upper circle *slides* over the arc  $AN$ , since the two circles



must be always tangent, both  $C$  and  $A$  must move with the same angular velocity about  $D$ . This being true of two points in the moving circle, must be true of all other points; the movement above supposed would therefore bring  $C$  to




FIG. 27.




FIG. 28.


$C'$ , and  $E$  to  $E'$ ,—the arcs  $AN, CC', EE'$ , all having the common centre  $D$ , and measuring equal angles.

32. That is to say, the motion represented by the arrow  $t$  is one of *revolution* about  $D$ , the centre of curvature of the

base line  $LM$ —which in Fig. 27 is one of straight translation simply because the radius of curvature of  $LM$  is, in that case, infinite.

In either case, the linear velocity of  $A$ , due to the rotation about  $C$ , indicated by  $r$ , is equal and opposite to that due to the revolution indicated by  $t$ ; the point of contact being therefore at rest for the instant.

This fact of itself seems almost conclusive proof that the



**FIG. 29.**

point in question is the instantaneous axis of the moving piece: this, however, is capable of still more general and rigorous demonstration, which we give here, because the fact is of importance in relation to some combinations presently to be considered, and ought therefore to be firmly established.

33. In Fig. 29, neither the fixed nor the moving curve is circular, but  $C$  is the centre of curvature of the lower one, and  $D$  that of the upper one, at their common point  $A$ ; therefore  $CD$  is their common normal. Let  $o, s$ , represent points on these curves consecutive to, and equidistant from,  $A$ . Then, if the upper curve *slide* upon the lower, the point  $o$  can be brought into coincidence with  $A$  of the lower curve only by a rotation about  $D$ , indicated by the arrow  $r$ ; and the point  $A$  of the upper curve can be brought into coincidence with  $s$  only by a revolution about  $C$ , indicated by the arrow  $t$ . Let the linear velocities of the point  $A$  of the upper curve, due to these motions, be represented by  $Ax$ ,  $Az$ , and let these be equal to each other, since  $Ao, As$ , are equal by hypothesis.

Now let  $P$  be any point rigidly connected to the moving curve. The motion of  $P$  will be the resultant of rotations about  $D$  and  $C$ ; the components are therefore perpendicular to  $PD$  and  $PC$ , respectively, and as their values we shall have

$$\left. \begin{aligned} PH &= \frac{Ax \cdot PD}{AD}, \\ PE &= \frac{Az \cdot PC}{AC}. \end{aligned} \right\} \therefore \frac{PH}{PE} = \frac{PD \cdot AC}{PC \cdot AD}. \quad (1).$$

Completing the parallelogram, the diagonal  $PR$  is the resultant motion of  $P$ . Next draw  $PA$ , and also  $AN$  parallel to  $PC$ , and  $AK$  parallel to  $PD$ . We shall then have:

$$\left. \begin{aligned} \frac{PN}{PD} &= \frac{AC}{CD}, \therefore PN = \frac{PD \cdot AC}{CD}, \\ \text{and} \\ \frac{PK}{PC} &= \frac{AD}{CD}, \therefore PK = \frac{PC \cdot AD}{CD}, \end{aligned} \right\} \therefore \frac{PN}{PK} = \frac{PD \cdot AC}{PC \cdot AD}. \quad (2).$$

The second members of Equations (1) and (2) being identical, their first members are equal; i.e.,  $\frac{PH}{PE} = \frac{PN}{PK}$ .

But the angles,  $HPE$ ,  $NPK$ , are equal; therefore the parallelograms  $HE$ ,  $NK$ , are similar, and the angles  $RPE$ ,  $APC$ , are equal. Consequently,

$$EPA + RPE, = RPA, \text{ is equal to } EPA + APC, = EPC.$$

Now  $EPC$  is a right angle by hypothesis; therefore  $PR$ , the absolute motion of  $P$ , is perpendicular to a right line drawn from  $P$  to the point of tangency  $A$ . Since  $P$  was chosen at pleasure, it follows that lines perpendicular to the motions of any other points connected rigidly with the moving curve, will intersect in  $A$ , which must therefore be the instantaneous axis of that curve: and it is perfectly clear that a rotation about  $A$  will bring the point  $o$  into coincidence with  $s$ , which we have already seen to be a condition of rolling contact.

34. The utility of this fact is well illustrated in Fig. 30, which shows a simple planetary train. The shaft of the wheel  $W'$ , which rolls around the fixed wheel  $W$ , has its bearings in the crank or "train-arm"  $CD$ , and, projecting through that arm, has secured upon it a second crank  $DA$ . The crank-pin  $A$  operates the link  $AP$ , of which the opposite end  $P$  is caused by guides, not shown, to travel in the line  $CP$ . The point  $A$  traces the epitrochoid shown in dotted line; and its position, for any given position of  $CD$ , is readily found as follows: starting with the two cranks coinciding in one right line  $Cda$ , and  $m$  as the point of contact, set off, on the two circles, equal arcs  $mO$ ,  $mo$ ; then in the rolling,  $o$  will go to  $O$ ,  $od$  then becoming the contact radius  $OD$ , while the angle  $oda$  will remain unchanged.

The motion of  $A$ , for any assigned velocity of  $D$ , might




FIG. 30.

be determined as in Fig. 22, since it is the resultant of a revolution around  $C$  and a rotation about  $D$ ; these are essentially independent of each other, notwithstanding the engagement of the two wheels, which is but one of many possible methods of fixing the relative directions and velocities of those two motions.

But the determination can be made in a much more simple and direct manner, because  $O$  is the instantaneous axis. Let  $DN$  be the motion assigned to  $D$ ; then the motion of  $A$  must be perpendicular to the *instantaneous radius*  $OA$ , and its velocity  $AM$  is found by making the angle  $AOM$  equal to the angle  $DON$ .

If it be further required to find the velocity of  $P$ , the argument is, that on the prolongation of  $AP$  a component should be set off equal to  $AL$  the absolute component of  $AM$ , and at its extremity a perpendicular to  $AP$  should be erected, which would cut  $CP$  produced, at a point limiting the required resultant. This, obviously, would result in the construction of a right-angled triangle similar and equal to  $ALR$ , formed by drawing through  $A$  a parallel to  $CP$ , cutting  $ML$  (produced if necessary) in  $R$ ; which gives  $AR$  as the required velocity of  $P$ . This abbreviation may evidently be employed in any case where the motion of one end of a link is given, and that of the opposite end in a given direction is required.

35. Fig. 31 also exhibits a simple planetary combination, in which, however, the central (or sun) wheel  $W$  is not fixed, but turns freely about the axis  $C$ . The planet-wheel  $W'$  is rigidly secured to the connecting-rod  $LP$ , the point  $P$  being made to travel in the line  $CP$ ; and the two wheels are kept in gear by means of the link  $CD$ . This arrangement is known as "Watt's sun-and-planet wheels," having been em-



ployed by the illustrious engineer as a substitute for the crank, upon which, as connected with a rotative steam engine, some one had secured a patent.

If, now, we assign to  $D$  a velocity  $DN$ , the motion of  $P$  is ascertained, as usual, by making  $PQ$  equal to  $DB$ , the absolute longitudinal component of  $DN$ , and drawing  $QR$  perpendicular to  $DP$ . It is next to be noted that the motion of  $W'$  consists of a revolution about  $C$  and a rotation about its own centre  $D$ ; and the same is true of the motion of  $P$ , since it is rigidly connected with that wheel. Resolving  $PR$  accordingly,  $PE$  is the component of revolution, and  $PF$  that of rotation. The angular velocity of the revolution is represented by the angle  $PCE$ , which of course is equal to  $DCN$ ; and  $AJ$  is the linear velocity of  $A$ , due to this motion. The angular velocity of the rotation is represented by the angle  $PDF$ , and  $LI$  is the additional circumferential velocity due to that motion, to which  $JM$  is made equal, giving  $AM$  as the actual velocity of  $A$ : and  $ACM$  represents the angular velocity of  $W$ .

**36.** A test of the accuracy of both the analysis and the construction may be applied by producing  $DC$  to cut the prolongation of  $EP$  in  $O$ , the instantaneous axis of the planet-wheel and its attached rod. Draw  $NO$  and  $RO$ ; then the two angles marked  $\beta$  should be equal, and  $NO$  should pass through the point  $M$ : also it is to be observed that when  $O$  is accessible, this affords the readiest means of determining  $AM$  when  $DN$  is given, and *vice versa*.

It is quite apparent that if the velocity of  $D$  is constant, the velocity of  $W$  will vary, unless  $DP$  is infinite,  $W'$  then having a motion of circular translation; on the other hand, if  $W$  turns uniformly, the motion of  $D$  will be variable. Consequently the law of variation in the piston speed will



be different in an engine in which this arrangement is used, from that obtaining in one provided with an ordinary crank, the main shaft revolving uniformly in each case. If the circumferential velocity of  $W$  be assigned, as  $AM$ , the velocity of  $P$  may be found thus: draw  $PA$  and produce it, find the absolute component  $AK$  along that line, make  $PH$  equal to it, and draw  $HR$  perpendicular to  $PA$ ; otherwise find the instantaneous axis  $O$ , and make the angle  $POR$  equal to the angle  $AOM$ .

37. In Fig. 32, the engaging wheels of which  $W, W'$ , are the pitch circles, turn about the fixed centres  $D$  and  $C$ . In the front face of  $W'$  is fixed a pin  $B$ , turning freely in a block, which slides in a slot formed in one arm of a bent lever; this lever turns about the fixed centre  $E$ , and in the extremity  $F$  of the other arm is a pin upon which is hung a swinging lever  $FP$ : from the front face of  $W$  projects a pin  $A$ , connected with the free end of the swinging lever by a link  $AP$ . Considering  $A$  as the driving point, and assigning to it a motion  $AM$  (necessarily perpendicular to the radius  $DA$ ), it is required to determine the motion of  $P$ .

Produce  $DA$  to  $J$  on the circumference of  $W$ , at which point draw a tangent, limited by its intersection at  $L$  with the prolongation of  $DM$ ;  $JL$  thus determined is the circumferential velocity of  $W$ . That of  $W'$  is necessarily the same; therefore, producing  $CB$  to cut the circumference at  $J'$ , draw the tangent  $J'L'$  equal to  $JL$ ; draw  $CL'$ , and at  $B$  draw a perpendicular to  $CB$ , cutting  $CL'$  in  $N$ ; then  $BN$  is the linear motion of  $B$ . Resolve  $BN$  into two components, one in the line  $BE$ , the other perpendicular to it; the longitudinal component merely produces a sliding of the block in the slot, but the side component  $Bd$  establishes a rotation of the bent lever about  $E$ , of which the angular velocity is



represented by the angle  $\beta$ , or  $BEd$ . The point  $F$  must have the same angular velocity, and must move in a direction perpendicular to  $EF$ , so that its linear velocity  $FQ$  is determined by constructing the angle  $\beta'$  equal to  $\beta$ , and the absolute component of  $FQ$  along  $PF$  is  $F\epsilon$ , to which  $Pe'$  must be equal.

Returning now to the pin  $A$ ; its motion  $AM$  has an absolute component  $Aa$  in the line  $AP$ , to which  $Pa'$  must be equal. Then, erecting at  $a'$  a perpendicular to  $AP$ , and at  $\epsilon'$  a perpendicular to  $FP$ , the intersection  $R$  of these perpendiculars is the extremity of the required resultant motion  $PR$ .

**38.** In Fig. 33, the planet-wheel  $W'$ , which rolls inside the fixed annular sun-wheel  $W$ , has its bearings at the extremity  $C$  of one arm of a bent lever  $CDE$ , which turns about  $D$  the centre of  $W$ . At the extremity  $E$  of the other arm of this lever, is the bearing of a pin which projects from the farther side of the arm or lever  $EF$ , and is made in one piece with it. The lower end of this arm is formed into a sleeve, through which slides freely the rod  $BS$ , perpendicular to  $EF$ ; this rod is formed, at the left-hand end, into an eye, fitted upon a pin  $B$ , which is fixed in the planet-wheel and projects from its front face. Finally, to the free end of  $EF$  is pivoted the link or connecting-rod  $FP$ , of which the farther end  $P$  is made to travel in the line  $PD$ .

Suppose for the moment the annular wheel  $W$  to be removed, and the bent lever  $CDE$  to be stationary, while  $W'$  revolves about  $C$  as a fixed centre. Then it is to be noted that the kinematic action of the virtual crank-arm  $CB$  and the bent lever  $BEF$  is precisely the same in this figure as in the preceding one; in this case the sliding in the direction  $BE$  occurs in the sleeve at  $E$ , whereas in Fig. 32 it




FIG. 33.

was accommodated by the motion of the block at  $B$  in the slotted arm  $BE$ . In either case, then, the rotation of  $B$  about  $C$  causes  $F$  to vibrate in a limited arc about  $E$ . Now when  $W$  is replaced and  $CDE$  is made to revolve about  $D$ , this vibration goes on as before, so that the length of the virtual crank-arm  $DF$ , by which  $P$  is actuated, is continually varying within certain limits. Let  $C$  turn about  $D$  as indicated by the arrow  $t$ , then  $W'$  will rotate about  $C$  in the direction shown by the arrow  $r$ .

39. Assign to  $C$  a velocity  $CM$ , then its angular velocity about the instantaneous axis  $A$  will be represented by the angle  $CAM$ ; the motion of  $B$  will be perpendicular to the instantaneous radius  $AB$ , and its linear velocity  $BN$  is determined by making the angle  $BAN$  equal to  $CAM$ . The motion of  $E$  is  $EL$  perpendicular to  $DE$ , the angle  $EDL$  being made equal to the angle  $CDM$ . The absolute components of  $BN$  are  $Bb$ ,  $Bn$ ; those of  $EL$  are  $Ee$ ,  $Ek$ . Join the extremities of the side components by the line  $be$ , cutting  $BE$  in  $I$ . This point is the instantaneous centre about which  $BS$  is rotating; and by reason of the connection between  $EF$  and  $BS$ , it is clear that  $EF$  must also rotate about  $I$ , in the same direction and with the same angular velocity. Therefore the motion of  $F$  has a component of rotation  $FK$  perpendicular to  $FI$ , the angle  $FIK$  being made equal to the angle  $EIk$ ; and also a component of translation  $Fh'$  parallel and equal to  $Ek$ . Completing the parallelogram, the motion of  $F$  is the diagonal  $FG$ . This has a component  $FJ$  in the line of  $PF$ , to which  $PQ$  is equal; then draw at  $Q$  a perpendicular to  $PF$  cutting  $PD$ , the line of travel, in  $R$ , and  $PR$  is the resultant motion of  $P$ .

40. Now, the point  $E$  is common to  $BS$  and  $EF$ , and both pieces have the same instantaneous centre  $I$ ; consequently

their instantaneous axes must lie in a perpendicular to  $BS$  through  $I$ . This perpendicular cuts the prolongation of  $AB$  in  $O$ , which is the instantaneous axis of  $BS$ ; and it cuts  $DE$  in  $O'$ , the instantaneous axis of  $EF$ . The actual motion of the point  $E$  on  $BS$  is  $EH$ , the resultant of the components  $Ee$ , and  $En'$  equal to  $Bn$ , and  $OE$  is perpendicular to  $EH$ ; (incidentally, the sliding at  $E$  is equal to  $Ek + En'$ ): also,  $O'F$  is perpendicular to  $FG$ , the motion of  $F$ .

Again, the actual motion in space of the line  $EF$ , is determined by the two motions  $EL$ ,  $FG$ ; the absolute components of  $EL$ , as above seen, are  $Ek$ ,  $Ee$ ,—those of  $FG$  are  $Fg$ ,  $Fe'$ . Draw  $gh$  cutting  $EF$  in  $I'$ ; then it is seen that the motion of  $EF$  may be regarded as a rotation about  $I'$  as an instantaneous centre, combined with a longitudinal translation in the line  $EF$ .

41. And this motion is equivalent to a rotation about an instantaneous axis, which must lie in a perpendicular to  $EF$  through the point  $I'$ ; this perpendicular must, therefore, pass through  $O'$ , which has already been shown to be the instantaneous axis. And since all the longitudinal components must be equal, it follows that  $Fe' = Ee$ . Also since at  $I'$  there is no side component, the absolute motion of that point is in the direction  $FE$ , and equal to  $Ee$ . In the small diagram at the left, this motion,  $I'e''$ , is seen to be the resultant of a rotative component  $I'k$ , perpendicular to  $II'$  (the angle  $I'Ik$  being equal to the angle  $EIe$ ), and a component of translation  $I'h''$ , equal and parallel to  $Ek$ .

42. A peculiar device for producing aggregate motion, the action of which is at first glance rather obscure, is shown in Fig. 34. It consists of a crank  $AD$ , turning about the fixed centre  $D$ ; a connecting-rod  $AB$ , and a lever  $BC$ , which vibrates about  $C$  as a fixed centre. Upon the pin  $B$  are




FIG. 34. PILGRIM-STEP MOTION.

hung the wheels  $W$  and  $X$ ; these are secured together, and turn freely on the pin, and  $X$  engages with a wheel  $Y$ , which turns freely about its centre  $C$ .

A wheel  $U$  is secured to the crank  $AD$ , and communicates motion to  $W$  through the intervention of an idle wheel  $V$ , whose bearing is the pin  $E$ , fixed in the connecting-rod.

In this arrangement the crank  $AD$  is the driver, and the ultimate follower is the wheel  $Y$ ; given the velocity of the crank-pin  $A$ , then, the problem is to find the circumferential velocity of that wheel.

It needs no argument to show that if this problem be attacked analytically, any formula expressing the action of such a train will be so complicated as to render the solution tedious, if not difficult; but if treated graphically it is both simple and easy, and requires only the application of principles already explained.

Supposing the crank to turn to the right, let  $AM$  represent the motion of  $A$ . Resolve  $AM$  into the rectangular components  $Aa$ ,  $Ab$ , and set off  $Ba'$  equal to  $Aa$ ; draw at  $a'$  a perpendicular to  $AB$ , and at  $B$  a perpendicular to  $BC$ ; these intersect in  $N$ , and  $BN$  represents the motion of  $B$ . At  $P$ , the point of contact between the circumferences of  $X$  and  $Y$ , draw  $PQ$  perpendicular to  $BC$ , and limited by its intersection with  $CN$ . Suppose for the moment the wheel  $W$  to be removed; there would then be nothing to cause  $X$  to rotate about  $B$ , so that  $X$ ,  $Y$ , and  $BC$  would move as one piece, turning about  $C$ , and  $PQ$  would represent the circumferential velocity of the wheel  $Y$ .

But when  $W$  is restored, this value  $PQ$  will be affected by two things; of which the more important is due to the rotation of  $V$  about its centre  $E$ , caused by its engagement with  $U$ , which is secured to the crank  $AD$ .



In order to determine the velocity of this rotation, draw  $TT$ , tangent to  $U$  and  $V$  at their common point  $F$ , and join  $bb'$  the extremities of the side components of  $AM$  and  $BN$ . Then  $bb'$  cuts  $TT$  in  $O$ , and  $FO$  is the tangential component of the point  $F$  on the circumference of  $V$ , supposing  $U$  to be removed. But  $F$  is also a point on the circumference of  $U$ , and its absolute motion when so considered is  $FG$ , perpendicular to  $FD$ , and limited by constructing the angle  $FDG$ , equal to the angle  $ADM$ . Draw  $GH$  perpendicular to  $TT$ ; then  $FH$  is the tangential component, and  $OH$  is the circumferential velocity of  $V$ , in its rotation about  $E$ —the direction being as indicated by the arrow  $v$ . This rotation will impart to  $W$  an equal circumferential velocity; therefore we make  $KJ$ , the common tangent of  $V$  and  $W$ , equal to  $OH$ . Draw  $JB$  to limit  $LS$  tangent to  $X$  and parallel to  $JK$ , then  $LS$  should be in this case added to  $PQ$  on account of the rotation of  $V$  about its centre  $E$ .

43. But this is not all; as previously stated, the value  $PQ$  is affected by another thing, which is due to the motion of the link  $AB$  (carrying  $V$  with it), in relation to  $BC$ . This will be clear when it is considered that if  $V$  did not turn at all about  $E$ , but moved as though fixed to the link, the point  $K$  on its circumference would still have a motion  $Kj$ , determined by the intersection of  $bb'$  with  $KJ$ , which also would be imparted to  $W$ . Draw  $jB$  cutting  $LS$  in  $s$ ; it will then be clear that  $PQ$  must in this case be increased by an amount  $QR$  equal to  $LS + Ls$ , which gives  $PR$  as the circumferential velocity of the last wheel in the train.

It is apparent that the motion  $Ls$  is due to the folding up of the link  $AB$  upon the lever  $PC$ ; which will continue until the lever reaches the position  $C_2$ , the extreme limit of its outward excursion. On the return, the directions of

both  $PQ$  and  $Ls$  will be reversed ; and the actual velocity of  $P$  will be  $PQ + Ls - LS$ , since the rotation of  $V$  about  $E$  goes on continuously in the same direction.

It is also evident that  $LS$  is always greater than  $Ls$  ; so that, while the wheel  $Y$  turns first in one direction and then in the other, it is driven farther to the left than to the right during each reciprocation of the lever  $BC$ , and consequently it will ultimately make complete revolutions about its centre  $C$ , in the direction of the arrow  $y$ .

Now, because the motion of a point in the circumference of  $Y$  is reciprocating, and of less velocity in one direction than in the other, it follows that a "velocity diagram" representing the motion will be of the general form  $ABCDE$  in Fig. 35 ; the point  $A$  representing the instant when the wheel begins to turn in the direction of the arrow, the point  $C$  the instant of reversal, and the point  $E$  the instant when it again comes to rest. Since all this is accomplished during one revolution of the driving crank,  $AE$  represents the time occupied by that revolution, of which the velocity is uniform.

44. Obviously it is desirable that such a diagram should begin and end at zero. But in this case we are confronted at the outset by the question, at what position of the crank is the wheel at rest ? Clearly it is easy enough to determine the dead centres 1, 2, of the crank, and the corresponding positions 1, 2, of the pin  $B$  ; at which instants the lever  $BC$  is at rest : but at either of those instants the wheel  $Y$  will be found to have a definite velocity, which may be determined by the processes above set forth.

In such a case the construction of the velocity diagram is the readiest means of determining the required dead points of the driven wheel. In Fig. 36, make  $FL$  equal to

$AE$  of Fig. 35; place the crank in the position  $1D$ , the lever in the position  $1C$ , determine the velocity of  $P$ , and set up the ordinate  $FG$  equal to it; then the ordinate  $LM$  will plainly be equal to  $FG$ . Without entering into the details of the construction, suppose the velocity diagram  $GHJM$  to

FIG. 35.




FIG. 36.

be drawn; this curve will cut  $FL$  at the points  $I, K$ , which represent the instants when  $Y$  is at rest.

Then supposing the crank-pin  $A$ , in Fig. 34, to start from point  $1$  upon its circular path (which corresponds to  $F$  in Fig. 36), divide the circumference of that path into parts proportional to  $FI, IK, KL$ . The points of division corresponding to  $I$  and  $K$  will then be the positions of the crank-pin at the instants when the wheel  $Y$  is at rest; and the positions of the lever  $BC$  at those instants can then be readily found in the usual manner.

Now if, in Fig. 36, we set back  $FN$  equal to  $LK$  and copy

the portion  $MK$  in the position  $GN$ , we shall have the curve  $NHIJK$ , the required diagram, identical in form and arrangement with  $ABCDE$  in the preceding figure.

45. A further example of planetary wheel-work forms part of the combination shown in Fig. 37.

The central, or "sun," wheel  $W$  is stationary, as shown by the screws securing it to the frame.

The shaft  $D$  of this wheel turns freely in its bearings, and an eccentric is keyed upon it, in which are the bearings of the shaft of the planet-wheel  $W'$ , whose centre is  $C$ ; thus the eccentric itself forms the train-arm. The shaft  $C$  has keyed upon it the wheel  $W'$  at the back, and the crank  $CE$  is in front of the eccentric; the eccentric-rod is pivoted at  $B$  to a sliding socket which moves upon guides; and this socket carries a pin  $F$ , upon which turns one end of the lever  $FP$ ; and this lever is connected with the crank  $CE$  by a link  $EH$ . Now, supposing the eccentric to turn about  $D$  at a given rate, it is required to determine the direction and velocity of  $P$ 's motion at the instant when the parts occupy the position shown.

The centre of the eccentric is  $A$ ; let  $AM$  be the motion assigned to it; then  $CM'$ , the velocity of  $C$ , is found as shown by prolonging  $DM$ .

Now, the crank  $CE$  and the wheel  $W'$  being virtually one piece, are at the instant rotating about the instantaneous axis  $I$ , the point of contact between the sun-wheel and its planet.

Therefore, drawing  $IM'$ ,  $IE$ , and  $EL$  perpendicular to  $IE$ , then  $EL$ , limited by making the angle  $EIL$  equal to the angle  $CIM'$ , will be the motion of  $E$ ; this has a component  $Eg$  in the direction of  $EH$ , to which  $Hg'$  in the same direction must be equal. Draw  $AB$  and produce it, making  $Ba'$



equal to  $Aa$ , the component of  $AM$  in the line  $AB$ ; and draw  $a'N$  perpendicular to  $Ba'$  to determine  $BN$ , the motion of  $B$ , to which the motion  $FJ$  of the point  $F$  is parallel and equal. Then, with reference to  $FP$ ,  $FJ$  has the side component  $Fc$ , and the longitudinal component  $Fd$ ; and both  $Hd'$  and  $Pd''$  in the direction  $FP$  must be equal to  $Fd$ .

Draw at  $d'$  a perpendicular to  $FP$ , and at  $g'$  a perpendicular to  $EH$ ; these intersect in  $K$ , and  $HK$  is the resultant motion of  $H$ , which has a side component  $He$ . The prolongation of  $ce$  will limit the side component  $Pf$  of the motion of  $P$ ; the longitudinal component is  $Pd''$ , and the diagonal  $PR$  of the completed rectangle is the required resultant motion; and  $JKR$  will be a right line parallel to  $cef$ , if the construction has been correctly made.

46. In Fig. 38,  $W$  is the pitch circle of a wheel formed in one piece with an eccentric keyed upon the shaft  $D$ ; for the sake of avoiding confusion, this pitch circle is drawn of the same diameter as the eccentric.

As in the preceding figure, the eccentric rod is pivoted at  $B$  to a piece which slides upon guides, and carries a projecting pin  $G$ , upon which turns the lever  $GP$ . Then  $A$  being the centre of the eccentric, and  $AM$  representing its motion, the motions  $BN$  and its equal  $GV$  are determined as in Fig. 35, so that no more need be said of them.

The eccentric rod in this case has a projecting portion on the upper side, in which is fixed a pin  $C$ , with a wheel  $w$  turning freely on it; and  $w$  engages with  $W$ . The smaller wheel has also a projection from its front face, in which is fixed a pin  $E$  by which a link is pivoted to it, whose other end is pivoted at  $P$  to the lever  $GP$ . Then, knowing  $AM$ , we are to ascertain the motion of  $P$  in velocity and direction. To begin with, since  $GV$  is already known, we find




FIG. 38.

with reference to  $GP$  its side and longitudinal components,  $Gh$  and  $Gm$ ; then, since  $Pm'$  must be equal to  $Gm$ , it remains to find the absolute component of the motion of  $P$ , or, what is the same thing, of  $E$ , in the line of the link  $EP$ .

Now, considering the wheel  $w$  by itself, it turns on its bearing at  $C$  solely by reason of its engagement with  $W$ ; so that, if the latter were removed, it would move as one piece with the eccentric rod. And the motion of that rod consists in a rotation about  $I$  (the intersection of  $AB$  with the line  $bb'$  joining the extremities of the side components of the motions of  $A$  and  $B$ ), combined with a translation in the direction  $AB$ ,—and the magnitude  $Aa$  of the latter is already known.

The wheels  $W$  and  $w$  touch each other at the point  $O$  on  $AC$ ; then  $Oc$ , perpendicular  $OI$ , of such length that the angle  $OIc$  is equal to the angle  $AIb$ , is the rotative component of the point  $O$  on the connecting-rod; the component of translation is  $Oa''$  equal and parallel to  $Aa$ , and  $OQ$ , the diagonal of the completed parallelogram, is the resultant motion, which would be the same for the point  $O$  on the smaller wheel were the larger one removed.

47. But the motion of the point  $O$  on the wheel  $W$ , is  $OS$  perpendicular to  $OD$ , limited by making the angle  $ODS$  equal to the angle  $ADM$ . Now draw  $TT$ , the common tangent to the two wheels, and upon it let fall the perpendiculars  $QE'$ ,  $SJ'$ ; these, of course, should be equal to each other and to the normal components of the motions  $OQ$ ,  $OS$ . The tangential components  $OE'$ ,  $OJ'$ , lie in the same direction, so that their difference  $EJ'$  represents the circumferential velocity of the rotation of  $w$  about  $C$ . For the sake of perspicuity we have placed the point  $E$  upon the circumference of  $w$ , so that  $EJ$ , perpendicular to  $CE$ , and equal to  $EJ'$ , is



one component of the motion of  $E$ , and is due solely to the engagement of the two wheels. But were  $W$  removed,  $E$  would be to all intents and purposes a point of the connecting-rod; and its motion might be determined (since the instantaneous axis is inaccessible) just as  $OQ$  was, which is the method here exhibited;  $Ed$  perpendicular to  $EI$ , making the angle  $EId$  equal to the angle  $AIb$ , is one component, while  $Ea'''$  equal and parallel to  $Aa$ , is the other; then  $EK$  the diagonal of the completed parallelogram is the resultant motion upon this supposition. Finally, complete the parallelogram  $JEKL$ , and its diagonal  $EL$  is the resultant motion of  $E$  when the whole mechanism is set in action; this has a component  $El$  in the line  $PE$ , to which  $P'l'$  must be equal; erecting at  $l'$  and  $m'$  perpendiculars to  $PE$  and  $PG$ , respectively, they intersect in  $R$ , and  $PR$  is the resultant required.

In reference to  $PG$ , the side components at  $P$  and  $G$  are  $Pg$ ,  $Gh$ ; draw  $gh$  cutting  $PG$  in  $f$ , and at this point erect a perpendicular to  $PG$ ; this should pass through  $F$ , the instantaneous axis of  $PG$ , which is the intersection of  $PF$ ,  $GF$ , respectively perpendicular to  $PR$  and  $GV$ .

#### SIMULTANEOUS DEAD-POINTS IN LINK-WORK.

48. In the train of link-work shown in Fig. 39, the driving crank  $DA$ , by means of the connecting-rod  $AB$ , imparts a vibratory movement to the lever  $CE$ ; which, in its turn, causes the bent lever  $FGH$  to vibrate through the intervention of the link  $EF$ ; finally, to this bent lever is pivoted the link  $HP$ , whose extremity  $P$  is constrained by guides (not shown) to travel in the vertical line  $IL$ . And the problem is, assigning any velocity to the crank-pin  $A$ , to determine the resultant velocity of  $P$ .

Now this combination, consisting as it does of simple levers and links, presents no new feature, except in the two critical positions when the crank-pin  $A$  reaches either  $a$




FIG. 39.

or  $a'$ . The proportions here given are such that  $CG = CE - EF + FG$ ; so that when  $A$  reaches either of the above-mentioned points, the centre lines  $CE$ ,  $EF$ , and  $FG$ , coincide in one line  $CfeG$ : the link being thus folded up upon both levers, we have two simultaneous dead-points.

It is stated by Prof. Rankine ("Machinery and Mill-work," p. 193), that in these circumstances the ratio of the angular velocities of the two levers is *indeterminate*; were this so, then the ratio between the linear velocities of the points  $E$  and  $F$  would also be indeterminate. I propose to show that neither of these things is true.

Since the motions of  $E$  and  $F$ , in the position under consideration, are both perpendicular to the line joining those points, the motion of the link must, at the instant, be one of rotation about some point on  $EF$  or its prolongation, and the first step is to find that point; the method of doing this




FIG. 40.

is illustrated in Fig. 40. The upper part of this figure gives a side view of two levers  $CA$ ,  $DB$ , connected by a link  $AB$ , at the instant of collapse. In the movement diagram below, it must be understood that  $CV$ ,  $DY$ , do not represent *positions* of the levers, but that  $AV$ ,  $BY$ , and  $HW$ , represent

the *motions* of the points  $A$  and  $B$ , and of  $H$  the required instantaneous axis, at the critical instant.

The actual magnitudes of these lines are immaterial, but the relative velocities must be such, and  $H$  must be so situated, in all cases, as to satisfy the following conditions, viz.:

1. Because the link  $AB$  is, at the instant, turning about  $H$  as a centre, the line  $YV$ , or its prolongation, must pass through  $H$ .

2. Because  $H$  is the virtual intersection of the centre lines of the levers  $AC$  and  $BD$ , the magnitude of  $HW$  must be such that the prolongations of  $CV$  and  $DY$  shall pass through  $W$ .

49. The lines of this diagram form three pairs of similar right-angled triangles, from which the following proportions are readily deduced, viz.:

$$\left. \begin{array}{l} \frac{AV}{HW} = \frac{AC}{HC} \\ \frac{HW}{BY} = \frac{HD}{BD} \end{array} \right\} \therefore \frac{AV}{BY} = \frac{HA}{HB} = \frac{HD}{HC} \times \frac{AC}{BD}.$$

Or, substituting the symbols given in the figure,

$$\frac{x}{x+l} = \frac{R-l-x}{x+r} \times \frac{r}{R};$$

whence

$$x^2 - \frac{2rl}{R+r}x = \frac{Rlr - rl^2}{R+r},$$

and this gives

$$x = \frac{\pm \sqrt{Rlr(R-l+r)} - rl}{R+r}.$$

Which proves that the distance of the instantaneous axis  $H$  from the point  $A$  is not indeterminate, but must have one

of two definite and easily ascertained values: and the ratio of the linear velocities of the points  $A$  and  $B$  is the same as the ratio of their distances from the instantaneous axis,—*i.e.*,

$$\frac{AV}{BY} = \frac{HA}{HB}.$$

In the figure the proportions are as follows:  $R = 6$ ,  $r = 3$ ,  $l = 2.25$ , and the resulting values are,  $AH = +1.087$ ,  $AH = -2.587$ . The first value is the one taken in Fig. 40; the result of taking the second is shown in Fig. 41. It is




FIG. 41.

apparent that the diagrams can not be constructed with certainty until these values have been computed; though the rudest sketch will serve the purpose in making the calculations.

50. The ratio of the linear velocities being, then, determinate, and the lengths of the levers fixed, the ratio of their angular velocities must also be determinate. In order to find its value, let  $v$  represent the angular velocity of  $R$ ,  $v'$  represent the angular velocity of  $r$ ; then, since angular velocity =  $\frac{\text{linear velocity}}{\text{radius}}$ , we shall have

$$\left. \begin{aligned} v &= \frac{BY}{R}, \\ v' &= \frac{AV}{r}. \end{aligned} \right\} \therefore \frac{v}{v'} = \frac{BY}{AV} \times \frac{r}{R} = \frac{HB}{HA} \times \frac{r}{R}.$$

Or, since  $HA = x$ , and  $HB = x + l$ ,  $\frac{v}{v'} = \frac{r(x+l)}{Rx}$ ; whence, substituting in this equation the value of  $x$ , already found, and reducing, we have finally

$$\frac{v}{v'} = \frac{\pm r \sqrt{Rlr(R-l+r)} + Rlr}{\pm R \sqrt{Rlr(R-l+r)} - Rlr}.$$

This expression, with the assigned lengths of the link and levers, gives the values,

$$\frac{v}{v'} = \frac{77}{50} \text{ (very nearly), for Fig. 40.}$$

$$\frac{v}{v'} = \frac{13}{200} \quad \text{“} \quad \text{“} \quad \text{“} \quad \text{Fig. 41.}$$

51. Now a question of at least theoretic interest arises in regard to the action of the mechanism shown in Fig. 39. It is usually held, I believe, that only the component in the line of the link is effective in transmitting either force or motion from one lever to another. And, so long as there is any such component, there is no occasion, and, it may be said, no ground, for questioning the correctness of that dictum. Nor yet in the case of a single dead centre; thus, in Fig 39, the link  $AB$  merely rotates about its instantaneous axis  $B$ ; which is at the instant stationary, for the simple reason that it can not move both ways at once: so, although there is no component in the line of the link, no motion nor force is transmitted to the lever  $CBE$ .

But we may imagine  $BD$  in Fig. 40 to drive, with a constant velocity, for a limited distance on each side of the critical position; in that case the velocity of  $AC$  will be variable, of course, but it will not vanish at the instant of collapse, notwithstanding the fact that there will then be no component in the line of the link—for it has been shown that it must have a definite value as compared with that of  $BD$ . This arrangement, then, seems to present a remarkable exception to the general proposition referred to, whether regarded kinematically or dynamically.

52. It may be (and has been) said that owing to the elasticity of materials, to the impossibility of securing absolute freedom from “play” or lost motion,—in short, to the perverse nature of inanimate things and to all that prevents the realization of abstract desiderata, there will practically be a small rotation about  $A$  at the critical instant; after which there *would* be a longitudinal component of motion or of force. Were this the true explanation, this component would be very small in comparison with its effective lever arm, unless the rotation about  $A$  were very considerable; from which it would follow that the levers would “go hard” across the line of centres; and that the more, the better the fitting. So that, were the fitting absolutely perfect, the levers could only cross the line of centres by the aid of momentum, even if friction were entirely eliminated; and if once stopped upon that line, no force applied to either lever could move the other.

53. But a study of the action of a model made for the Stevens Institute of Technology leads me to the conclusion that the exact contrary is the case. The proportions of this model are the same as those of the figures accompanying this article; and the levers pass the critical position with the

greatest ease. From which it would seem that the link at that instant acts as a lever whose fulcrum is the instantaneous axis, and operates by side pressure instead of by end-long thrust or pull.

Another interesting point in regard to the action of the model is this: that when the levers are placed on the line of centres, the mechanism exhibits no hesitation in making a choice between the two possible positions of the instantaneous axis. If the lever  $BD$  is the driver, the combination moves as indicated by the diagram in Fig. 40; but when  $AC$  is the driver, the motions correspond to Fig. 41.

It may be added, in conclusion, that the dead points may also occur simultaneously when the two levers point in the same direction; and since the proportions may be varied in many ways, the diagrams may present appearances very unlike those here given. But this method of reasoning may be applied in all cases; and in no one of them will the velocity ratio be found indeterminate.

**"SLOW ADVANCE AND QUICK RETURN" MOTION PRODUCED  
BY ELLIPTICAL WHEELS.**

54. In Fig. 42,  $C$  and  $D$  are the fixed centres of a pair of elliptical wheels, in contact at  $P$ . In order that these may move in continuous rolling contact, the two ellipses must be identical, each must be centred upon one of its foci, and the distance between the fixed centres must be equal to the major axis; in practice, both wheels must be provided with teeth, which are omitted in the diagram, since the action is best seen and discussed by consideration of the pitch curves only.

Since the point of contact must always lie upon the line of centres  $CD$ , its motion must be perpendicular to that line,



and its linear velocity is the same whether it be regarded as belonging to one ellipse or the other, so that the angular velocities are inversely proportional to the contact radii ; thus, letting

$v$  = ang. vel. about  $D$ , and

$v'$  = " " "  $C$ , we have

$$\frac{v}{v'} = \frac{PC}{PD}, \text{ in the present position,}$$

and setting off the equal elliptical arcs  $PEK$ ,  $PIJ$ , then, when  $J$  and  $K$  meet, we shall have

$$\frac{v}{v'} = \frac{JC}{KD}; \text{ or, drawing } JC \text{ and joining } K \text{ with}$$

$F$ , the free focus of the right-hand ellipse, this latter value may be written

$$\frac{v}{v'} = \frac{KF}{KD}.$$

In order to bring  $K$  and  $J$  into coincidence, it is apparent that while the driver turns as indicated by the arrow, through the angle  $PDK$ , the follower must turn in the opposite direction through the angle  $PCJ$ ; and this, it is to be noted, is equal to the angle  $PFK$ .

55. These ellipses are so situated and proportioned that  $PC$  and  $PF$  are respectively perpendicular to the major axes; and, producing these lines to cut the ellipses in  $H$  and  $G$ , the arcs  $PIH$  and  $PEG$  are equal; whence it follows that while the driver turns through the angle  $GDP$ , the follower will have made a half revolution.

While it is making the other half, the driver must complete its own, thus turning through an angle much greater

than  $GDP$ ; since the two ellipses have equal perimeters and necessarily revolve in equal times about their fixed centres of rotation.

Now let a pin, fixed in the follower at any point  $A$  in the major axis, actuate a link whose farther extremity  $B$  is constrained by guides (not shown) to travel in the line of that axis, then the traverse of  $B$  along that line will be equal to  $AL = 2AC$ ; it will make the upward stroke while the driver turns through the angle  $GDP$ , and the downward stroke while the driver is completing its revolution. If, then, the driver turns uniformly, the down stroke of  $B$  will occupy a greater time than the up stroke; which is just what is required in a shaping machine, which calls for a "slow advance" of the tool-holder while making the cut, and a "quick return" for saving time while no work is done. As here arranged, the cut would be made on the down stroke, and by the "pull" of the link; this is merely for the sake of saving space in the illustrative diagram; and it will be evident that had  $B$  been below  $A$  instead of above, the condition would have been reversed, the work being done by the "push" of the link; both arrangements have been used in practice, but the kinematic action is the same whichever be adopted.

56. Now if, in the design of a shaping machine to be actuated by elliptical wheels as above shown, the ratio of the times to be occupied by the advance and the return be assigned, the first thing is to determine the eccentricity of the ellipses which will satisfy the requirement: the manner of doing this may also be illustrated by Fig. 42. Let the time of the return be to the time of the advance as  $m$  is to  $n$ , for instance; then about any point  $D$  on the indefinite horizontal line  $HN$  describe a circle with any radius  $MD$ .

Divide the upper semicircumference into a number of equal parts represented by  $m + n$ , and set off  $MF$  equal to  $m$  parts, then  $FN = n$  parts. Draw  $DF$  and produce it; this will be the direction of the major axis of the driver: draw at  $F$  a perpendicular to  $DF$ , cutting  $HN$  in  $P$ ; then  $P$  is a point upon the ellipse, of which  $D$  and  $F$  are the foci, and the major axis is equal to  $PF + PD$ . On  $HN$  set off  $PC$  equal to  $PF$ ; produce  $FP$  to  $A$ , making  $PA$  equal to  $PD$ ; then  $C$  and  $A$  will be the foci of the other ellipse. In the figure, the advance is assumed to occupy three times as many seconds as the return; that is to say,  $m = 1$ ,  $n = 3$ , consequently the semicircumference  $MFN$  is divided into 4 equal parts, and  $MF$  being made equal to one of these parts,  $FN$  is equal to the other three.

It need hardly be added that the link may be operated by a crank keyed in any convenient position upon the shaft of the driven ellipse, with the understanding that it must be upon a dead centre when the ellipses occupy the relative positions shown in Fig. 42.

57. Our problem now is, to construct a diagram representing the varying velocity of  $B$  throughout the revolution of the driving ellipse, whose angular velocity is assumed to be constant. In order to do this, we must be able to determine at any given instant the motion of the crank-pin  $A$  (which, for the sake of simplicity only, has been placed in the focus of the driven ellipse). The *direction* of  $A$ 's motion is known, being always perpendicular to  $AC$ , which line revolves about  $C$  in a direction opposite to that of the driver. In determining its *velocity*, we have only to remember that angular velocity may be represented by the linear velocity of a point at unit distance from the axis (the magnitude of this unit, for purposes of comparison, being arbitrary); and

FIG. 43.





FIG. 42.

we have already shown that the angular velocities of the driver and follower are inversely proportional to the radii of contact, at any given instant.

Assuming then, in Fig. 42,  $CA$ , which is equal to  $DF$ , as the unit distance, and assigning to  $F$  any linear velocity at pleasure; from what precedes we shall have, when for instance  $J$  and  $K$  meet upon the line of centres,

$$KF:KD::\text{lin. vel. } F:\text{lin. vel. } A.$$

The required velocity of  $A$  may then be easily determined graphically as in Fig. 43. Upon either of two lines intersecting in  $K$  at any convenient angle, set off from  $K$  the distances  $KF, KD$ , taken from Fig. 42; on the other line set off  $KV$ , the assigned linear velocity of  $F$ ; draw  $VF$ , and through  $D$  a parallel to it, cutting the prolongation of  $KV$  in  $V'$ ; then  $KV'$  is the required linear velocity of  $A$ , since by similar triangles we have

$$KF:KD::KV:KV'.$$

58. We repeat in Fig. 44 the construction for determining the velocity of  $B$  when that of  $A$  is known;  $AC$  representing the position of the crank,  $AB$  that of the link, and  $CB$  the line of travel. Let  $AM$ , perpendicular to  $AC$ , represent the velocity of  $A$ ; this has a component  $Am$  in the line of the link, to which  $BN$  must be equal. Then drawing at  $N$  a perpendicular to  $AB$ , cutting  $CB$  in  $R$ , we have  $BR$  as the resultant velocity of  $B$ . This work may be abbreviated by drawing  $AR'$  parallel to  $CB$ , and limited by the prolongation of  $Mm$  perpendicular to  $AB$ , since the triangle  $AmR'$  thus formed, is similar and equal to  $BNR$ .

Now, in constructing a velocity diagram such as is required, it is clearly advisable not to select random points

or contact between the driver and follower, like  $K$  and  $J$  in the preceding illustrations, but to proceed in an orderly and




FIG. 44.




FIG. 45.

systematic manner. For the purpose of showing clearly how this may be done, we have in Fig. 45 reproduced the driving ellipse in the same position as in Fig. 42;  $PD$  being

the initial contact radius, and  $PDG$  the angle through which the driver turns during the "quick return" stroke of  $B$ . About the fixed focus  $D$ , describe a "measuring circle" large enough to lie well outside the ellipse, as in the figure, and produce  $DP$ ,  $DG$ , to cut its circumference. Divide the quadrant which measures the angle  $PDG$  into any number of equal parts, and from the points of division, 1, 2, 3, etc., draw radii to  $D$ , cutting the perimeter of the ellipse at  $a$ ,  $b$ ,  $c$ , etc.; from these points draw finally the lines  $aF$ ,  $bF$ , etc., to the other focus of the ellipse.

The points  $a$ ,  $b$ , etc., will evidently become contact points at equal intervals of time; and as each one does so, the corresponding positions and velocity of the crank-pin  $A$  are to be determined as above explained in reference to the point  $K$  in Figs. 42 and 43, and finally the velocity of  $B$  for each position is to be found as in Fig. 44.

59. These values of the velocities of  $B$  are the ordinates of that portion  $XUY$  of the curve in Fig. 46, which pertains to the return stroke. Any distance  $XY$  on the line of abscissas, representing the time occupied by that stroke, is divided into as many equal parts as the quadrant in Fig. 45; any point of subdivision, as  $b$  for instance, represents the instant when the corresponding point of the ellipse in the preceding figure becomes a contact point, and the ordinate represents the velocity of  $B$  at that instant.

Since the advance stroke is made during the remaining three-fourths of the revolution, that fraction of the measuring circle is next divided into any convenient number of equal parts as indicated by the figures 1, 2, 3, etc., inside the circumference in Fig. 45; in Fig. 44,  $YZ = 3XY$ , is similarly subdivided, and the diagram is completed by setting up at each point an ordinate representing the velocity of  $B$  at the

instant represented by that point, ascertained by constructions identical with those already explained.

Now, since the abscissas represent times and the ordinates represent velocities, and since also

$$\text{Time} \times \text{Velocity} = \text{Space},$$

it is clear that the areas of the two curves  $XUY$ ,  $YWZ$ , should be equal, each representing the length of the stroke.

60. By the mode of construction, as seen in Fig. 42, the major axis of the driving ellipse bisects the angles through which it turns during both strokes. And it is practically advantageous to subdivide both these angles so that, as in Fig. 45, the successive contact points upon that ellipse, which are made use of in determining the ordinates of the velocity diagram, shall be symmetrically disposed with respect to that axis. Because, the ratio of the focal distances, and therefore the velocity of the crank-pin  $A$ , will be the same for  $a$  and  $e$ , for  $b$  and  $d$ , and so on, thus saving much time in determining the velocities of  $A$ . In regard to the number of ordinates to be determined, it is impossible to give any specific directions; but, in constructing these or any other curves, it is plain that the points through which they must pass should be nearest each other where the curvature changes most rapidly; as, for instance, in the region of  $U$  the vertex of the return stroke-curve in Fig. 46.

61. Another diagram of interest is given in Fig. 47, where the curve  $UVW$  represents the varying *angular* velocity of the driven ellipse, the constant velocity of the driver being represented by the horizontal line  $MN$ . Since the driver and the follower turn in opposite directions, it would, perhaps, be more consistent to place  $UVW$  and  $MN$  on opposite sides of  $AB$ ; but the directional relation in



a case like this is hardly likely to be lost sight of, and the varying velocity can be more readily compared with the constant one by adopting the arrangement shown in the figure.

The ordinates of this curve are the linear velocities of




FIG. 46.




FIG. 47.

B, as determined in constructing the preceding diagram. The velocity of *A* will be greatest when *E* of Fig. 42 (corresponding to *c* of Fig. 45) is the driving point of contact, and least at the end of a half revolution, when the

opposite ends of the major axes come together. In the former position we shall have for the velocity ratio,  $\frac{v'}{v} = \frac{ED}{EF}$ , and in the latter  $\frac{v'}{v} = \frac{EF}{ED}$ , the one value being the reciprocal of the other; and if either of these positions be selected as the initial one, it is clear that the resulting diagram will be symmetrical with respect to its central ordinate, because the ellipse is symmetrically divided by its major axis.

We prefer to make the first ordinate the least, as  $AU$  in Fig. 47, where  $AM$  represents the constant velocity of the free focus of the driver, and is equal to  $KV$  in Fig. 43. Since each ellipse completes its revolution in the same time, it follows that the area of the curve  $UVW$  must be equal to that of the rectangle  $AN$ , and that the areas of the shaded portions  $UMX$ ,  $XZc$ , must be equal to each other.

62. It may be added that in using elliptical wheels for this purpose, the writer hereof has shown that any given ratio between the times of the advance and the return may be secured by means of ellipses whose eccentricity varies between certain limits, so that a given pair of elliptical wheels might be used for shaping machines with different conditions as to the relative times of advance and return: in the course of the investigation it was also demonstrated that for a given ratio between those times, the construction illustrated in Fig. 42 gives the *minimum eccentricity*.

This is a point of practical importance; for since it is clearly impossible to preserve a running balance in the rotating parts of mechanism of this description, it is as clearly advantageous to reduce the unavoidable vibration to the lowest attainable limit.

## OTHER "SLOW ADVANCE AND QUICK RETURN" MOTIONS.

**63.** In Fig. 48 is represented the device known as "the crank and slotted arm," which in various forms has been extensively used for producing the slow advance and quick return motion in shaping machines.  $D$  is the fixed centre of the driving crank, whose pin  $P$  turns in a block which slides freely in the slotted arm  $CA$ , of which  $C$  is the fixed centre. To the extremity  $A$  of this arm is jointed a link, of which the other extremity  $B$  is constrained by guides (not shown) to travel in the line  $KH$ . The excursion of the arm  $CA$  is plainly limited by the lines  $CG$ ,  $CI$ , tangent at  $E$  and  $F$  to the circular path of  $P$ .

With  $G$  and  $I$  as centres, describe with radius  $AB$  arcs cutting the line of travel of  $B$  in  $H$  and  $K$ ; these points limit the traverse of  $B$  in its assigned path. When  $P$  is in the position shown, let  $PO$  perpendicular to  $PD$  represent its linear velocity.

Resolve  $PO$  into components  $PV$  in the line  $AC$ , and  $PL$  perpendicular to it; the former represents the sliding, which is accommodated by the slot, and the latter,  $PL$ , is the linear velocity of the point  $P$  in the line  $CA$ , in rotation about  $C$ . Therefore,  $AM$ , perpendicular to  $AC$ , and limited by the prolongation of  $CL$ , is the linear velocity of  $A$ . The component of  $AM$  in the direction  $BA$  is  $AN$ , to which  $BQ$  must be equal, and a perpendicular to  $BA$  at  $Q$  cuts the line  $KH$  in  $R$ , giving  $BR$  as the resultant velocity of  $B$ .

As in previous cases, this may be abbreviated by drawing through  $A$  a parallel to  $KH$ , cutting  $MN$  produced in  $T$ ; since the triangle  $ANT$  thus formed is similar and equal to  $BQR$ .

**64.** In this arrangement it is obvious that the arm  $CA$

FIG. 48.




FIG. 48a

will swing through the arc  $IG$  while the driving crank turns through the arc  $FPE$ , and  $A$  will return from  $G$  to  $I$  while the crank turns through the remaining part of the circumference,  $EF$ .

Consequently, if the ratio between the times of the advance and return be assigned, as for instance as  $m$  is to  $n$ ; describe a circle about any centre  $D$  with any radius  $DP$ , divide its circumference into  $m + n$  parts, and make  $EF$  equal to  $n$  parts; then  $EPF = m$  parts. At  $E$  and  $F$  thus determined, draw tangents to the path of  $P$ , intersecting at  $C$ : this determines the proportions of the moving pieces and the relative positions of the fixed centres—it being obvious that the lengths of  $CA$  and of  $AB$ , as well as the direction of  $B$ 's travel, are entirely arbitrary in theory, although in practice they are limited by various considerations which need not here be discussed.

The link, indeed, may be dispensed with altogether; thus in Fig. 48a, the outer extremity  $A$  of the slotted lever is formed into a pin projecting from the front side of the lever; this pin works between jaws formed on a piece  $S$ , by which the cutting tool is carried, and this piece is constrained by guides (not shown) to travel in the direction of the arrow. In this case, the motion  $AM$  of the point  $A$  is to be resolved into the components  $AX$ , and  $AY$ ; the former alone is effective, and represents the resultant motion of the sliding head  $S$ .

65. This combination has also been used in a curvilinear slotting machine, the tool being carried directly by a curved extension of the vibrating arm, as shown in Fig. 49. This figure represents an application to the work of reducing the thickness of portions of the rim of a locomotive driving-wheel  $W$ , when the latter had proved not to be in correct

running balance : as described and illustrated in Professor Goodeve's "Elements of Mechanism."

FIG. 49.




FIG. 49a.

The crank is here replaced by a disk, provided with a slot to enable the pin  $P$  to be fixed at a greater or less distance from the centre  $D$ , in order to regulate the length of the stroke. This adjustment, however, affects the ratio between the times of the advance and return ; as the effective crank-arm is diminished, the relative time of the return will be increased. This will be clear by the aid of Fig. 47a,

where it is obvious that the angle  $DCE'$  is less than the angle  $DCE$ , and since the angles at  $E'$  and  $E$  are both right angles, it follows that  $CDE'$  is greater than  $CDE$ .

**66.** In Fig. 50 is shown the modification of the "crank and slotted arm" device known as the Whitworth motion; it differs from the preceding in that the centre  $C$  lies within the path of  $P$  instead of outside of it, so that  $CA$  makes a complete rotation for each revolution of the driving crank. The path of  $P$  is divided at  $E$  and  $F$ , exactly as in the preceding case, for the purpose of securing any desired ratio between the times of the advance and return; the chord  $EF$  is then bisected in order to locate  $C$ ; and this chord is also the line of travel, in the practical use of the movement. In determining the speed of  $B$  when that of  $P$  is assigned, the proceeding is precisely the same as in Fig. 48, and since the two diagrams are lettered similarly throughout, no further explanation is required.

**67.** It is very evident that the device shown in Fig. 50 is in that form perfectly impracticable as a working machine, since the shaft  $C$  would interfere with the crank  $DP$ , if it projected behind  $CA$ , while if it projected in front of the slotted arm it would interfere with the link  $AB$ . These difficulties were most ingeniously evaded by the distinguished inventor, and an extremely serviceable machine constructed in the manner illustrated in Fig. 51. The crank is here replaced by a wheel  $W$ , riding loose upon a fixed shaft whose centre is  $D$ , and driven by a pinion  $w$ ; in the front face of this wheel is fixed the driving crank-pin  $P$ . The fixed shaft  $D$  has bored in it a hole at  $C$ , as shown more clearly in Fig. 52. Into this hole projects a pin forming a part of the piece  $SS$ , Fig. 51, at the back of which is a slot in which slides a block fitted upon the pin  $P$ . In the front




FIG. 50.






FIG. 51.

FIG. 52.





face of *SS* there is also a slot in which the pin which drives the link *AB* can be fixed in any desired position.

By varying the distance between *A* and *C*, then, the length of the stroke may be controlled at pleasure; but in this case there is no change in the ratio between the times of the advance and the return, since the relative positions of *P*, *D*, and *C*, which fix this ratio, are not affected by any variation of *AC*.

68. Another method of producing a slow advance and quick return movement, by the use of levers and links only, is shown in Fig. 53. In this combination, the driving crank *DA*, by means of the link *AB*, actuates the vibrating lever *BC*. To the extremity, *B*, of this lever is pivoted the link *BP*, whose free end, *P*, is constrained to move to and fro in the path *HK*.

Supposing as before that the time of traverse in one direction along *HK* is to be to the time occupied in the return as *m* is to *n*, the skeleton movement is laid out thus: about any centre *D* describe a circle with any assumed radius, as *DA*; and divide the circumference at *E* and *F* so that *EAF* = *m* parts, while *FE* = *n* parts, as in the preceding cases. Assuming any reasonable length for the first link *AB*, set off *EDI* equal to this assumed length; this locates the point *I*, the crank being at an inward dead point. Next draw *DF* and produce it, making *FG* also equal to *AB*; then *G* is the extremity of this link when the crank is at an outward dead point. Draw *IG*, bisect it by a perpendicular, and on the bisector take any point *C* as the fixed centre of the vibrating lever *CB*; in practice the angle *ICG* should never exceed 60°, and if possible it should be less: the length of *BP* and the line of travel of *P*, are clearly arbitrary.



link, we have adhered to the direct process, by means of the longitudinal component of the motion of the driving point; because the reasoning is clear and simple, and perfect familiarity with that method is essential. We now proceed to explain one or two other methods, which in some cases are more expeditious, although the reason why they are correct is not by any means so obvious.

Fig. 54 shows the crank and connecting-rod of a direct-acting steam-engine, the cross-head pin  $O$  travelling in the horizontal line  $OC$ . At  $C$  erect the vertical line  $CX$ , and produce the line of the connecting-rod  $OP$ , if necessary, to cut  $CX$  in the point  $A$ . Then, if the velocity of  $P$  is represented by a line equal to  $CP$ , the velocity of  $O$  will be represented by a line equal to  $CA$ .

For, setting off  $PM$  perpendicular and equal to  $PC$ , and drawing  $MB$  perpendicular to  $PA$ , and  $PB$  perpendicular to  $CA$ , the triangle  $PAC$  is similar and equal to the triangle  $PMB$ . And it has already been shown that if  $PM$  is the velocity of  $P$ ,  $PB$  is equal to the velocity of  $O$ ; and  $CA$  is equal to  $PB$ .

If for any reason it is desirable to represent the velocity of the crank-pin by a line greater or less than  $CP$ , as for instance  $CL$ , it will now be obvious that, drawing  $LK$  parallel to  $OP$ , we shall have  $CK$  equal to the velocity of the cross-head pin.

71. Fig. 55 also represents the crank and connecting-rod of a direct-acting engine. In this construction,  $PR$ , the velocity of the crank-pin, of any magnitude at pleasure, is set off on the prolongation of  $CP$ ; draw through  $R$  a parallel to  $PO$ , cutting at  $T$  a vertical line through  $O$ , then  $OT$  is equal to the velocity of  $O$ . For, first setting off as before  $PM$  perpendicular to  $PC$  and equal to  $PR$ , draw  $PQ$  parallel

and equal to  $OT$ ,  $MB$  perpendicular to  $RQ$ , and  $PB$  perpendicular to  $PQ$ . Then the triangles  $PMB$ ,  $PRQ$ , are similar and equal, and we have  $PQ = OT$ ,  $= PB$ .

If we lay off the velocity  $CL$  from the centre  $C$ , and




FIG. 54.




FIG. 55.




FIG. 56.

draw  $LK$  parallel to  $PO$ , cutting the vertical through  $C$  in  $K$ , the triangles  $CLK$ ,  $PRQ$ , are similar, so that  $CK$  will be the velocity of  $O$ , as in Fig. 54.

72. In Fig. 56 we have two levers  $DP$ ,  $CO$ , connected by a link  $PO$ . The construction here is analogous to that of the preceding figure; setting off  $PR$ , the assigned velocity of  $P$ , on the prolongation of  $DP$ , draw through  $R$  a parallel to  $PO$ , cutting the prolongation of  $CO$  in the point  $T$ : then  $OT$  is the velocity of  $O$ . And the demonstration is also the same as before; for drawing  $PM$ ,  $= PR$ , perpendicular to  $DP$ , draw also  $PQ$  equal and parallel to  $OT$ ,  $MB$  perpendicular to  $RQ$ , and  $PB$  perpendicular to  $PQ$ ; we have then, by reason of the two similar and equal triangles,  $PQ = OT$ ,  $= PB$ .

In order to save the reader the annoyance of referring to preceding diagrams, we have in Fig. 56 repeated all the steps of the direct determination; thus,  $PF$  is the absolute longitudinal component of  $PM$ , and  $OE$  is equal to  $PF$ ;  $ON$ , the resultant motion of  $O$ , is perpendicular to  $CO$ , and is limited by drawing  $EN$  perpendicular to  $PO$ . Then, the triangles  $OEN$ ,  $PFB$ , being similar and equal, we have  $PB = ON$ .

And thus we see that the simplest demonstration that the expeditive processes are correct, is made by proving that they give results concordant with those of the original direct method.

73. We have already explained and illustrated the representation of varying *angular* velocity, in the case of a crank rotating continuously in the same direction. That is no doubt the case in which such a representation is most striking and most readily understood; but the same methods of construction are equally applicable in the case of the circular reciprocation of a vibrating lever, although the result does not appeal so directly to the eye, and the diagram is not quite so easily read.

To illustrate, we give in Fig. 57 a skeleton of the "crank and slotted arm" movement, like that in Fig. 48; and in Fig. 58, a time-diagram of the angular velocity of the vibrating arm  $AC$ . The slotted arm  $AC$  moves from the position  $CE$  to the position  $CF$  while the pin  $P$  of the driving crank travels through the arc  $EZF$ , and back again while the crank-pin describes the remaining arc of the circumference,  $FE$ ; in this instance the former arc is twice the latter,—that is, if used in a shaping machine, the time of the advance will be twice that of the return: consequently, in Fig. 58 we make




FIG. 57.




FIG. 58.

$HQ = 2QT$ . In Fig. 57 is shown the process of determining one ordinate of the required curve. Since angular velocity = linear velocity of a point at unit distance from the centre, the first step is to describe about  $C$  an arc  $BG$  with radius  $CB = DE$ . In this particular case this arc will be tangent to the arc  $EF$ , because  $EDC = 60^\circ$ , whence  $CD = 2DE$ .

74. Now, when the driving crank is in any position as  $DP$ , assign to  $P$  any velocity as  $PO$ ; the component  $PL$  perpendicular to  $PC$  is the velocity of the point  $P$  on  $PC$ . Then,  $PC$  cuts the arc  $BG$  at  $I$ ; and  $IK$ , perpendicular to  $PC$  and limited by  $LC$ , is the value of the ordinate sought. Then, in Fig. 58, divide  $HQ$  so that

$$Hi : iQ :: \text{arc } EP : \text{arc } PZF,$$

and set up the ordinate  $ik$  equal to  $IK$ .

Now, making  $HM = PO = \text{constant velocity } P$ , the rectangle  $HN$  represents the space traversed by the crank in the time  $HQ$ , which is the arc  $EZF$ ; and the area of the curve  $HJQ$  represents the space traversed by the point  $B$  in the same time, or the arc  $BG$ ,  $= \frac{1}{4} EZF$ : therefore the area of the rectangle should be four times that of the curve. On the return stroke, the ordinates are negative,  $QR$  is equal to  $PO$ , and since  $GB = \frac{1}{2} FE$ , the area of the curve  $QVT$  is half that of the rectangle  $QS$ .

It is hardly necessary to point out that the curves  $HJQ$ ,  $QVT$ , are symmetrical about their central ordinates  $JW$ ,  $UV$ , so that it is only necessary to determine the ordinates for one half of each.

75. At the outset, a "velocity diagram" was defined as a curve whose abscissas represent *times*, while the ordinates represent the velocities, linear or angular, of a moving point at the instants indicated by the feet of the ordinates.

This is what is distinctively called a "**velocity-time**" diagram, and attention has purposely been thus far confined to it alone, because we consider it to be the most explanatory, and most generally useful, method of graphically exhibiting the phenomena of varied motion: but it is not by any means the only method.

In Fig. 59, we have shown a skeleton of the "Whitworth Motion" (Fig. 50);  $DP$  is the driving crank,  $CA$  the slotted arm,  $AB$  the link,  $BC$  the line of travel. Assign to  $P$  any velocity at pleasure, determine from that the linear velocity of  $B$ , and set down, perpendicular to the line of travel, the ordinate  $Bz'$  equal to that velocity. Do the same for as many different positions of the crank and arm as may be deemed necessary, and draw a curve through the extremities of the ordinates, for both the advance and the return. This curve is technically called a **velocity-space** diagram, and the ordinates of course show the velocity of  $B$  in its different positions.


These same ordinates, it is clear, are the ones used in constructing the "velocity-time" diagram, Fig. 60: in the former the abscissas represent varying distances traversed, in the latter they represent the equal times of traversing them.

76. As a matter of interest, we give in Fig. 61 the angular velocity-time diagram for the same movement; in which  $AM$  is the constant angular velocity of  $P$ , and the curve  $UVW$  represents the varying angular velocity of  $A$ .

It is obvious from inspection of Fig. 59 that the minimum velocity  $AU$  will be reached when both the crank and the slotted arm are on the vertical line and pointing upward; and the maximum,  $ZV$ , after a half revolution from that position, when both point downward. The ordinates of the curve are numbered to correspond with the subdivisions of the circles of Fig. 59; and it is to be noted that the curve crosses the horizontal line  $MN$  at the point  $X$ , coincident with the ordinate 8-8, at which instant the slotted arm is horizontal.

The ratio of the time of advance to the time of return





is, in this particular case, two to one; but it is of interest to observe that the above coincidence will occur, whatever the ratio. This may be demonstrated by the aid of Fig. 62, where  $PB$  is the assigned velocity of  $P$ ,  $PF$  the component effective in driving  $CA$ , and  $AR$  the resultant velocity of  $A$ . We have then,

$$PF:PC::PB:PD, = CA,$$

$$\therefore PF.CA = PC.PB;$$

also,

$PC:CA::PF:AR,$   
 $\therefore PC.AR = PF.CA, = PC.PB,$  FIG. 6  
 whence,  $AR = PB \dots \dots \dots$  Q. E. D.




FIG. 62.

**77.** Varying velocity may also be represented by a curve drawn through the extremities of lines of different lengths radiating from one central point, forming what is called a *polar* velocity diagram. Thus in Fig. 63, the circle represents the path of the pin *A* in Fig. 59; its circumference is similarly subdivided, and on the radii are set off the corresponding angular velocities, taken from Fig. 61. The resulting curve, then, serves to show the angular velocity of the slotted arm in any given position.

In Fig. 64, the circle represents also the path of  $A$  in Fig. 59, but it is divided into equal parts like the path of  $P$  in that figure. The distances set off on the radii are the same as in Fig. 63, and the polar diagram exhibits the angular velocities of the slotted arm at equal intervals of time. And it is quite obvious that similar diagrams could be made to represent the *linear* velocities of  $A$  at different points, or at different times.

78. Fig. 65 represents the crank, link, and vibrating lever movement that was given in Fig. 53 as one means of pro-




FIG. 63.




FIG. 64.




FIG. 65.

ducing a slow advance and quick return motion. The linear velocities of  $B$  in its different positions are laid off from the

arc  $IG$  upon lines radiating from  $C$ , so that the resulting curve is in effect a modified velocity-space diagram in which the line of abscissas is a circular arc instead of a right line.

These velocities, as shown, are determined by the method of Fig. 56; and this figure incidentally shows another demonstration that the method is correct. For, when the parts are in the positions drawn in heavy lines,  $O$  is the instantaneous axis of the link; consequently, linear velocity  $A$  : linear velocity  $B$  ::  $OA$  :  $OB$ ; and the triangles  $OAB$ ,  $O3'3'$ , are similar.

79. Still another mode of representing varied motion is shown in Fig. 66, the movement being merely the crank, connecting-rod, and cross-head, of a direct-acting engine.




FIG. 66.

The circular path of the crank-pin is divided into equal parts at 1, 2, 3, etc., which represent equal intervals of time; and on the radii through these points are set out from the centre, the velocities of the cross-head pin at the corresponding instants: and the curve determined by these points on the radii is for some occult reason designated as a polar velocity-time diagram of the motion of the cross-head pin. The linear velocity of the crank-pin being here represented

by a line equal in length to the crank, the required velocities are, as is obvious on inspection, determined by the method of Fig. 54.

But it must be admitted that this diagram does not so instantly appeal to the eye, or explain its own message so clearly, as those do in which the radial ordinates, as in Figs. 63 and 64, indicate the velocities of the radii themselves in circular movement.

**80.** The utility of velocity diagrams is nowhere more conspicuous than in comparing the actions of different combinations which effect the same result.

For example, Fig. 67 is the skeleton of an oscillating engine, with the trunnions at the end of the cylinder; in Fig. 68 the trunnions are placed at the middle of the length of the cylinder; and Fig. 69 is the common crank and connecting-rod movement: the lengths of all the cranks are equal. Supposing the rotative velocity to be also the same, it is of interest to compare the piston speeds with each other, and also with the piston speed of another engine having an infinite connecting-rod, or slotted cross-head, of which no skeleton is given.

The velocity-time diagrams of these four arrangements, for one stroke from left to right, are given in Fig. 70. That for the engine with the infinite connecting-rod is the curve marked *A*; this, being a perfect sinusoid, is symmetrical about its central ordinate *a*, which is also the maximum, and equal to the constant velocity of the crank-pin; the crank-arm being at that instant vertical.

**81.** Curve No. 1 shows the piston speed of the oscillating engine of Fig. 67; the maximum ordinate *c*, is equal to *a*, but since this corresponds to that phase of the movement when the piston rod is tangent to the path of the crank-pin.

which does not occur until after the crank has passed the vertical line, this ordinate is some distance to the right of  $a$ .

The engine of Fig. 68 gives curve No. 2; this is quite similar to No. 1, but its maximum ordinate,  $d$ , is still further




FIG. 67.




FIG. 68.




FIG. 69.

to the right—the reason for which is quite apparent from a comparison of the two movements.

The engine of Fig. 69 gives the curve No. 3, which is strikingly different from either of the others, in having *two*

ordinates,  $a$  and  $b$ , which are equal to the velocity of the crank-pin: the maximum ordinate lies somewhere between these two, but there is no geometric process known for determining its exact location. If, however, as in the figure we find by trial and error the centre  $o$  of a circle which sensibly agrees with the curve for a reasonable distance in the region of the vertex, a vertical ordinate  $k$  through the centre will, it is safe to say, be as near to the precise position as is necessary for any practical purposes. Then the dis-




FIG. 70.

tance between  $a$  and  $k$  will be a certain fraction of the half-length of the line of abscissas; and if the same fraction of the quadrant be set off to the right from the vertical line in Fig. 69, the phase of the movement at which the piston has the maximum velocity will be practically determined.

But the phases of the movement at which the piston speed is equal to the crank speed, can be graphically determined in a very simple manner.

82. Thus in Fig. 71, the crank  $CA$  is vertical.  $AB$  is the connecting rod,  $AM$  the velocity of  $A$ , and  $Am$  the longitudinal component, to which  $Bn$  must be equal. Drawing  $nN$  perpendicular to  $AB$ , it is evident that the two triangles  $AmM$ ,  $BnN$ , are similar and equal, so that  $BN = AM$ . And this accounts for the fact that in Fig 70, curve No. 3 cuts curve  $A$  at the extremity of ordinate  $a$ ; the crank being vertical in both cases. In order to avoid confusion, the other phase is shown *below* the horizontal centre line in Fig. 71;




FIG. 71.

the relative positions of the parts being such that the prolongation of the connecting-rod  $FE$  shall pass through  $D$ , the lowest point of the path of the crank-pin. Let  $EG$ , perpendicular to  $CE$ , be the velocity of the crank-pin; draw  $GH$  perpendicular to  $FED$ , also  $EH$  parallel to the path of  $F$  and consequently perpendicular to  $CD$ , then  $EH$  will be the velocity of  $F$ . But by the construction the triangles  $CED$ ,  $GEH$ , are similar; and since  $CE = CD$ , it follows that  $HE = EG$ .

Now, if the lengths of the crank  $CE$  and the connecting-rod  $EF$  are assigned, there is no geometrical method of




locating  $E$  or  $F$ . But the locations of both points may be determined with great accuracy, by marking on the edge of a straight slip of paper, two points indicating the length of  $EF$ . Then, moving this slip around so that the point  $E$  shall always lie on the crank-path, while the edge of the slip passes through  $D$ , mark the corresponding location of  $F$  for a number of positions of  $E$ . The points thus marked determine a curve  $xy$ , which cuts the line of travel in the point  $F$ ; and an arc about this point as centre, with radius equal to the given length of the connecting-rod, intersects the path of the crank-pin at the required point  $E$ , determining the corresponding position  $CE$  of the crank.

Now, the differences between the results of these four arrangements are very decided, and of no small interest; and it is safe to say that these differences can be more readily compared, and are made more conspicuous, by the diagrams in Fig. 70, than they could be by any other means whatever.

**83.** As another example, let us consider the two slow advance and quick return motions shown in Figs. 72 and 73. The first is the Whitworth movement, which has already been described; the second was devised by the writer, with a view of avoiding the sliding in the slotted arm of the former. In order to do this, the two cranks are connected by a short link  $AB$ ; and the method of construction is shown in Fig. 74.

Describe about  $D$  a circle with radius  $DB$  the length of the driving crank, and divide its circumference so that the arc  $BMF$  shall be to the remainder of the circumference as the time of the return is to the time of the advance; draw  $BF$ , and bisect it by a perpendicular, which locates the fixed centre  $C$ . Next draw the link  $BA$  parallel to  $CD$ ;



the length of this link may be varied within narrow limits, but must always be greater than  $MN$  and less than  $MO$ ; and finally draw  $AC$ , the driven crank. If now we suppose the driver to turn in the direction of the arrow, it will be seen that while  $B$  describes the arc  $BMF$ ,  $A$  will have been driven through the arc  $ANE$ , or  $180^\circ$ , the two cranks then having the positions  $DF$ ,  $CE$ ; and that in order to make  $A$  describe the other semicircumference and return to its original position,  $B$  must travel through the remaining portion  $FEB$  of its own path.

This combination, clearly, is the well-known drag link;




FIG. 75.

but we have never met with any suggestion of using it for this particular purpose. In so applying it, the diameter  $ACE$  must, evidently, be the line of travel of the remote extremity of the link which moves the tool-holder, as shown in Fig. 73.

Now, these two movements have been drawn on the same scale, and constructed to have the same proportion between the times of advance and return; and there is a pronounced difference between the velocity-space diagrams.

But the most interesting and valuable comparison is that between the velocity-time diagrams, which, drawn on a larger scale, are in Fig. 75 shown as superposed; the line of abscissas, and the scale of the ordinates, being the same for each, exactly as in Fig. 70.

84. Again, comparisons between angular velocities may be advantageously made in the same manner. When one rotating piece has a *constant* angular velocity, this fact has already been illustrated (see Figs. 47, 58, 61). But in Fig. 76, the two equal reciprocating levers,  $BC$  and  $EF$ , both move with varying angular velocities; and it may be desirable to compare their variations.

The driving crank  $AD$  actuates the lever  $BC$  by means




FIG. 76.

of the link  $AB$ , thus causing  $B$  to traverse the arc  $JH$ , exactly as in Figs. 51 and 63; and  $BC$  actuates  $EF$  by means of another link  $BE$ . These two levers were made of the same length, it may be stated, simply to lessen the labor of construction; for taking that length as unity, the linear velocities of  $B$  and  $E$  at once represent their angular veloci-

ties. And the values of these velocities are the ordinates of the two curves shown in Fig. 77, the one drawn in the heavy line relating to the lever  $BC$ , and the other to the lever  $EF$ ; the area of the latter, it is seen, is the greater, as it obviously should be, since the arc  $KL$  is greater than  $HJ$ .




FIG. 77.

85. Now, if we divide the ordinates of one curve by those of the other in their order, we obtain a series of fractions; each of these has a numerical value, which is either equal to, or greater or less than, unity, and expresses the value of the velocity ratio at the corresponding instant. And by setting up ordinates with these values, we may construct a curve exhibiting the variations of the *angular velocity ratio*. By inspection of Fig. 77, it will be seen that the value of this ratio will be unity where the curves intersect, as at  $\delta$  on the right and at  $\zeta$  on the left, since there the ordinate is the same for each.

And since these ordinates become more nearly equal as we approach the zero points, it is clear that unity is the

limiting value when the ratio becomes  $\frac{0}{0}$ , as it does when the driving crank in Fig. 76 is on the dead centres.

In the nature of things a ratio conveys no idea of direction, so that in constructing such a curve the ordinates may all be set up on the same side of the line of abscissas, thus requiring but one line for unity value; and this has been done in Fig. 78, in which the line of abscissas is equal in




FIG. 78.

length to that in Fig. 77, and subdivided in the same manner.

The values of the ordinates were obtained by dividing those of the curve *aaa* in Fig. 77, by those of the curve *bbb*; but it is proper to state that all this work has been done upon a small scale, and for illustrative purposes only, and of course the results are by no means to be regarded as equal in accuracy to those exhibited in many of the preceding diagrams

This then shows that variable velocity ratios *may* be graphically represented by a curve. But a ratio is essentially a compound idea; and though its value at any instant may be represented by the ordinate of a curve, as in Fig. 78, such a curve conveys no idea of the actual velocities which


determine that value. Of the two, then, Fig. 77 is far more explanatory and withal more readily understood, since both terms of the fraction are shown at the same time and on the same ordinate. Still, there may be cases in which a comparison of variations in angular velocity ratio might be desirable; and then the construction shown in Fig. 78 may prove to be of great utility.

#### ACCELERATION.

**86.** We pass now to the consideration of some graphical operations which, while not directly connected with the construction of velocity diagrams as heretofore considered, are nevertheless closely related to it, and are of at least equal interest.

In Fig. 79, mark on the line of abscissas, beginning at zero on the left, the equidistant points 1, 2, 3, etc., each representing an instant; then the spaces between them will represent equal periods of time. Set up at 1 an ordinate  $1a$ , representing on any convenient scale the distance traversed by a moving point during the first period. Let the distance traversed during the first two periods be represented by an ordinate  $2b$ , twice as great as  $1a$ . At the end of three periods, let the distance be three times as great, at the end of four, four times as great, as indicated by the ordinates  $3c$ ,  $4d$ , and so on. It will then be obvious that the line drawn through the points  $a$ ,  $b$ ,  $c$ ,  $d$ , etc., will be a right line passing through the zero point; and also, that the difference between any two ordinates will represent the distance traversed by the moving point during the intervening period—thus,  $4d - 1a = 3d$ , the distance traversed during three of the equal periods first set off. Similarly, drawing through

at the horizontal line  $ce$ , we have  $de$  as the space traversed in the time  $ce$ , and since  $\frac{\text{space}}{\text{time}} = \text{velocity}$ ,  $\frac{de}{ce}$  represents the velocity at the instant  $j$ ; and if we regard  $ce$  as a unit of time,  $de$  itself will be equal to the velocity; and accordingly  $jd''$  is set up equal to  $de$ . In this case the velocity is clearly uniform—and may accordingly be represented by a horizontal line through  $d'$ ; as it is quite obvious that for any



**FIG. 79.**

other instant, as for instance  $t$ , the same process will give for the velocity,  $\frac{bg}{ag} = \frac{de}{ce}$ .


The line drawn through the extremities of the ordinates (in this case  $ad$ ) may properly be called the *line of displacement*; and it is straight because the differences between successive equidistant ordinates are equal. Had they been unequal, that line would have been a curve; as for example  $xy$ ; and let us suppose the conditions to be such that  $xy$  is tangent to  $ad$  at the point  $c$ . The velocity of the moving point at the instant  $\beta$ , being measured by the distance which it would travel in a unit of time if that velocity were uniform,



would clearly be the same as that just determined. And had that curve of displacement been assigned, the velocity at that instant would be ascertained by erecting an ordinate cutting the curve at  $c$ , drawing through that point a tangent line and also a horizontal line of a length  $ce$  representing the unit of time, and erecting the vertical line  $ed$ .

87. To illustrate a practical application of this process, let us take the crank and connecting-rod movement of Fig. 80; supposing the rotation to be uniform, the circumference is divided into equal parts, and the corresponding positions of the cross-head pin are determined as usual. Then the distances  $o1, o2, o3$ , etc., are set up as ordinates at the equidistant points  $1, 2, 3$ , etc., in Fig. 81, the spaces between them representing equal times; and thus we construct the time displacement curve as shown. The velocity at  $4$  is determined as above explained, and the same process being repeated for the other instants, we have a velocity diagram, derived from the curve of displacement; the whole process being entirely different from anything previously described. And setting up the ordinates of this curve at the correspondingly numbered positions in Fig. 80, we can construct the velocity-space diagram.

Now in order to test the accuracy of this new method by comparing it with the old, we must know the circumferential velocity of the crank-pin; this is found by means of the fact that, as has previously been shown, it is equal to that of the cross-head pin when the crank is vertical, that is to say, to the ordinate  $3-3$ . Applying this test, the results of the two methods were found to be identical, in this case; but so happy a coincidence is not always to be looked for, since the new process depends upon the accurate drawing of a series of tangents, which in dealing with a curve of



unknown geometrical properties is sometimes quite a difficult, not to say an uncertain task; particularly if the curve is very flat.

88. As to the theoretical correctness of this process, however, the argument given in connection with Fig. 79 would appear conclusive; but corroborative evidence is found by its application to a displacement curve of known properties, to which the tangent can be drawn by geometrical construction; of which Fig. 82 is a good example. In order to give the diagram a more convenient form, the times are set up on the vertical line, as at 1, 2, 3, etc., and the corresponding spaces, as 1, 4, 9, etc., are laid off on the horizontal line, and the time-unit is four times the space-unit. Since the spaces are proportional to the squares of the times, the displacement curve is a parabola, of which  $F$  is the vertex and the horizontal line through  $F$  is the axis; the tangent to which at any point is most conveniently drawn by aid of the property that the subtangent is bisected at the vertex. To draw the tangent at  $A$ , then, set off  $FG = FI6$ , and draw  $GA$ . By the same process as in Fig. 81, then, we have  $\frac{BC}{BA}$  as the value of the velocity at the instant 4, and  $BA$  being unity, we set off  $4a = BC$ .

Now to find the numerical value of  $BC$ , we have by similar triangles,  $\frac{BC}{BA} = \frac{FG}{FE}$ , or  $\frac{BC}{4} = \frac{16}{8}$ , whence  $BC = 8$ . If this process be repeated, we shall find in a similar manner that the velocities at the instants 1, 2, 3, etc., are respectively 2, 4, 6, etc., showing that the velocity diagram is a straight line, and agreeing with the well known law of falling bodies, that the velocity varies directly with the time, and the space with the square of the time.

89. Now, just as the difference between two consecutive ordinates of the displacement curve indicates the velocity (or the rate at which the displacement is changing), so the difference between two consecutive ordinates of the velocity curve indicates the acceleration, or rate at which the velocity is changing. And by applying to the latter curve the same process that was applied to the former, we may determine an acceleration curve as in Fig. 81, exhibiting this rate of change at each instant of the motion. Thus  $KP$  is tangent to the velocity curve at  $K$ , through which point the horizontal line  $KL$  is drawn, and  $\frac{PL}{KL}$  represents the acceleration at the instant 5; since  $KL =$  unit time, the ordinate 5-5 is made equal to  $LP$ . But it is measured *downward* from the line of abscissas, because  $P$  is below the horizontal  $KL$ , indicating that the velocity is undergoing retardation; which it obviously must be, since the maximum velocity was reached between the instants 3 and 4.

In Fig. 82, the time-velocity is represented by a right line, and as in Fig. 79, the application of this process will produce another right line, parallel to the axis on which the times are measured. The distance of this line of acceleration may be found thus: By similar triangles we have  $\frac{bc}{ab} = \frac{Dc}{DF}$ , or  $\frac{bc}{4} = \frac{10}{20}$ , whence  $bc = 2$ ; which accords with the other law of falling bodies, that the acceleration is constant, and equal to the velocity acquired at the end of the first instant, counting from the state of rest as zero.

90. This process may be and has been described as one of graphical differentiation; and correctly, too; for the ratio  $\frac{MN}{AM}$ , in Fig. 81, will remain the same, no matter how short

$AM$  may be, and when  $A$  and  $M$  become consecutive, the fraction  $\frac{MN}{AM}$  will become, in the language of the calculus, merely  $\frac{dy}{dx}$ , or the first differential coefficient of the curve of displacement, from which the velocity curve is derived by differentiation.

And similarly,  $\frac{PL}{KL}$ , representing the first differential coefficient of the second curve, represents also the second differential coefficient of the original one. But the explanation given in connection with Fig. 79 will, we think, make the matter clear to those not familiar with the language of analysis.

It is to be observed that in Fig. 81, the final ordinate  $66$  of the acceleration curve is equal to  $TR$ , to obtain which a tangent  $PT$  is drawn to the curve at its extremity, and  $6R$  is set off equal to the unit of time. Also,  $PT$  makes a greater angle with the horizontal, than any other tangent which slopes downward toward the right; and of those which slope downward toward the left, the greatest angle is made by the tangent at the zero point. Consequently, the maximum ordinates of acceleration and retardation respectively, correspond to the beginning and the end of the stroke; which is clearly as it should be in this case.

91. But it is by no means true in all cases; a good illustration of this is given in Fig. 83, where the velocity curve is that of the "quick return" of a Whitworth movement. Here it is evident that the inclination of the curve to the horizontal (which is measured by that of its tangent), increases as we recede from the zero point, until the point of contrary flexure is reached, when it reaches its maximum,

and so does the ordinate of the curve of acceleration. When the velocity is at a maximum, it is clear that the acceleration will be nil; the tangent is at that instant hori-




FIG. 83.

zontal, and after that it will slope downward to the right: and similar reasoning to the above applies to the negative acceleration, or retardation.

Since the motion begins at zero and ends at zero, it is clear that the retardation and the acceleration must exactly balance, so that the area of that part of the curve above the line of abscissas should be equal to the area of the part below.



# INDEX.

---

	PAGE
Absolute Components.....	5
Acceleration.....	106-113
Axis, Instantaneous.....	10
Centre, ".....	11
Components, Absolute.....	5
Longitudinal.....	4
Normal.....	12
Side.....	4
Tangential.....	12
Composition of Rectilinear Motions.....	3
Revolution and Rotation.....	26, 27
Contact Motions.....	12
Rolling.....	34-39
Dead Points, Simultaneous.....	60-66
Differentiation, Graphical.....	III, 112
Displacement, Line of.....	107
Instantaneous Axis.....	10
Centre.....	11
Intersection of Two Rotating Right Lines.....	18-22
Curved Lines.....	23
Line of Displacement.....	107
"Pilgrim-step" Motion.....	50-54
Planetary Wheelwork.....	40, 42, 47
Roberval's Method of Drawing Tangents.....	14
Rolling Contact.....	34-39
Simultaneous Dead Points.....	60-66



	PAGE
"Slow Advance and Quick Return" Motions.....	67-85
By Crank and Slotted Arm.....	78-81
Drag Crank.....	100-102
Elliptical Wheels.....	67-77
Links and Levers.....	84, 85
Whitworth's Motion.....	82, 83
Velocity Diagrams—Angular.....	75
Velocity Ratio.....	104, 105
Comparison of.....	97-104
Polar.....	93, 95
Space.....	90, 91
Time.....	2, 90, 91

# SHORT-TITLE CATALOGUE

OF THE  
PUBLICATIONS

OF  
JOHN WILEY & SONS,

NEW YORK.

LONDON: CHAPMAN & HALL, LIMITED.

ARRANGED UNDER SUBJECTS.

Descriptive circulars sent on application.  
Books marked with an asterisk are sold at *net* prices only.  
All books are bound in cloth unless otherwise stated.

## AGRICULTURE.

Armsby's Manual of Cattle-feeding.....	12mo,	\$1 75
Downing's Fruits and Fruit-trees of America.....	8vo,	5 00
Grotenfelt's Principles of Modern Dairy Practice. (Woll.)..	12mo,	2 00
Kemp's Landscape Gardening.....	12mo,	2 50
Maynard's Landscape Gardening as Applied to Home Decoration .....	12mo,	1 50
Stockbridge's Rocks and Soils.....	8vo,	2 50
Woll's Handbook for Farmers and Dairymen.....	16mo,	1 50

## ARCHITECTURE.

Baldwin's Steam Heating for Buildings.....	12mo,	2 50
Berg's Buildings and Structures of American Railroads....	4to,	5 00
Birkmire's Planning and Construction of American Theatres.	8vo,	3 00
“ Architectural Iron and Steel.....	8vo,	3 50
“ Compound Riveted Girders as Applied in Buildings .....	8vo,	2 00
“ Planning and Construction of High Office Buildings .....	8vo,	3 50
“ Skeleton Construction in Buildings.....	8vo,	3 00
Briggs's Modern American School Buildings.....	8vo,	4 00
Carpenter's Heating and Ventilating of Buildings.....	8vo,	3 00
Freitag's Architectural Engineering.....	8vo,	3 50
“ Fireproofing of Steel Buildings.....	8vo,	2 50
Gerhard's Guide to Sanitary House-inspection.....	16mo,	1 00
“ Theatre Fires and Panics.....	12mo,	1 50
Hatfield's American House Carpenter.....	8vo,	5 00
Holly's Carpenters' and Joiners' Handbook.....	18mo,	75
Kidder's Architect's and Builder's Pocket-book..	16mo, morocco,	4 00
Merrill's Stones for Building and Decoration.....	8vo,	5 00

Monckton's Stair-building.....	4to,	4 00
Patton's Practical Treatise on Foundations.....	8vo,	3 00
Siebert and Biggin's Modern Stone-cutting and Masonry..	8vo,	1 50
Wait's Engineering and Architectural Jurisprudence.....	8vo,	6 00
	Sheep,	6 50
“ Law of Operations Preliminary to Construction in En- gineering and Architecture.....	8vo,	5 00
	Sheep,	5 50
“ Law of Contracts.....	8vo,	3 00
Woodbury's Fire Protection of Mills.....	8vo,	2 50
Worcester and Atkinson's Small Hospitals, Establishment and Maintenance, and Suggestions for Hospital Architecture, with Plans for a Small Hospital.....	12mo,	1 25
The World's Columbian Exposition of 1893.....	Large 4to,	1 00

### ARMY AND NAVY.

Bernadou's Smokeless Powder, Nitro-cellulose, and the Theory of the Cellulose Molecule.....	12mo,	2 50
* Bruff's Text-book of Ordnance and Gunnery.....	8vo,	6 00
Chase's Screw Propellers and Marine Propulsion.....	8vo,	3 00
Craig's Azimuth.....	4to,	3 50
Crehore and Squire's Polarizing Photo-chronograph.....	8vo,	3 00
Cronkhite's Gunnery for Non-commissioned Officers.....	24mo, mor.,	2 00
* Davis's Elements of Law.....	8vo,	2 50
* “ Treatise on the Military Law of United States..	8vo,	7 00
	Sheep,	7 50
De Brack's Cavalry Outpost Duties. (Carr.)....	24mo, morocco,	2 00
Dietz's Soldier's First Aid Handbook.....	16mo, morocco,	1 25
* Dredge's Modern French Artillery.....	4to, half morocco,	15 00
Durand's Resistance and Propulsion of Ships.....	8vo,	5 00
* Dyer's Handbook of Light Artillery.....	12mo,	3 00
Eissler's Modern High Explosives.....	8vo,	4 00
* Fiebeger's Text-book on Field Fortification.....	Small 8vo,	2 00
* Hoff's Elementary Naval Tactics.....	8vo,	1 50
Ingalls's Handbook of Problems in Direct Fire.....	8vo,	4 00
* “ Ballistic Tables.....	8vo,	1 50
Lyons's Treatise on Electromagnetic Phenomena.....	8vo,	6 00
* Mahan's Permanent Fortifications. (Mercur's.)	8vo, half mor.	7 50
Manual for Courts-martial.....	16mo, morocco,	1 50
* Mercur's Attack of Fortified Places.....	12mo,	2 00
* “ Elements of the Art of War.....	8vo,	4 00
Metcalf's Cost of Manufactures—And the Administration of Workshops, Public and Private.....	8vo,	5 00
“ Ordnance and Gunnery.....	12mo,	5 00
Murray's Infantry Drill Regulations.....	18mo, paper,	10
* Phelps's Practical Marine Surveying.....	8vo,	2 50
Powell's Army Officer's Examiner.....	12mo,	4 00

Sharpe's Art of Subsisting Armies in War.....	18mo, morocco,	1 50
Walke's Lectures on Explosives.....	8vo,	4 00
* Wheeler's Siege Operations and Military Mining.....	8vo,	2 00
Winthrop's Abridgment of Military Law.....	12mo,	2 50
Woodhull's Notes on Military Hygiene.....	16mo,	1 50
Young's Simple Elements of Navigation.....	16mo, morocco,	1 00
Second Edition, Enlarged and Revised.....	16mo, mor.,	2 00

### ASSAYING.

Fletcher's Practical Instructions in Quantitative Assaying with the Blowpipe.....	12mo, morocco,	1 50
Furman's Manual of Practical Assaying.....	8vo,	3 00
Miller's Manual of Assaying.....	12mo,	1 00
O'Driscoll's Notes on the Treatment of Gold Ores.....	8vo,	2 00
Ricketts and Miller's Notes on Assaying.....	8vo,	3 00
Wilson's Cyanide Processes.....	12mo,	1 50
" Chlorination Process .....	12mo,	1 50

### ASTRONOMY.

Craig's Azimuth.....	4to,	3 50
Doolittle's Treatise on Practical Astronomy.....	8vo,	4 00
Gore's Elements of Geodesy.....	8vo,	2 50
Hayford's Text-book of Geodetic Astronomy.....	8vo,	3 00
Merriman's Elements of Precise Surveying and Geodesy....	8vo,	2 50
* Michie and Harlow's Practical Astronomy.....	8vo,	3 00
* White's Elements of Theoretical and Descriptive Astronomy.	12mo,	2 00

### BOTANY.

Baldwin's Orchids of New England.....	Small 8vo,	1 50
Davenport's Statistical Methods, with Special Reference to Biological Variation.....	16mo, morocco,	1 25
Thomé and Bennett's Structural and Physiological Botany.	16mo,	2 25
Westermaier's Compendium of General Botany. (Schneider.)	8vo,	2 00

### CHEMISTRY.

Adrianee's Laboratory Calculations and Specific Gravity Tables,	12mo,	1 25
Allen's Tables for Iron Analysis.....	8vo,	3 00
Arnold's Compendium of Chemistry. (Mandel.) ( <i>In preparation.</i> )		
Austen's Notes for Chemical Students.....	12mo,	1 50
Bernadou's Smokeless Powder.—Nitro-cellulose, and Theory of the Cellulose Molecule.....	12mo,	2 50
Bolton's Quantitative Analysis.....	8vo,	1 50
Brush and Penfield's Manual of Determinative Mineralogy..	8vo,	4 00
Classen's Quantitative Chemical Analysis by Electrolysis. (Herrick—Boltwood.) .....	8vo,	3 00

Cohn's Indicators and Test-papers.....	12mo,	2 00
Craft's Short Course in Qualitative Chemical Analysis. (Schaeffer.) .....	12mo,	2 00
Drechsel's Chemical Reactions. (Merrill.).....	12mo,	1 25
Eissler's Modern High Explosives.....	8vo,	4 00
Effront's Enzymes and their Applications. (Prescott.) ( <i>In preparation.</i> )		
Erdmann's Introduction to Chemical Preparations. (Dunlap.)	12mo,	1 25
Fletcher's Practical Instructions in Quantitative Assaying with the Blowpipe.....	12mo, morocco,	1 50
Fresenius's Manual of Qualitative Chemical Analysis. (Wells.)	8vo,	5 00
“ System of Instruction in Quantitative Chemical Analysis. (Allen.) .....	8vo,	6 00
Fuertes's Water and Public Health.....	12mo,	1 50
Furman's Manual of Practical Assaying.....	8vo,	3 00
Gill's Gas and Fuel Analysis for Engineers.....	12mo,	1 25
Grotenfelt's Principles of Modern Dairy Practice. (Woll.)..	12mo,	2 00
Hammarsten's Text-book of Physiological Chemistry. (Mandel.)	8vo,	4 00
Helm's Principles of Mathematical Chemistry. (Morgan.)	12mo,	1 50
Holleman's Text-book of Inorganic Chemistry. (Cooper.)		
( <i>In preparation.</i> )		
Hopkins's Oil-chemists' Handbook.....	8vo,	3 00
Keep's Cast Iron. ( <i>In preparation.</i> )		
Ladd's Manual of Quantitative Chemical Analysis.....	12mo,	1 00
Landauer's Spectrum Analysis. (Tingle.).....	8vo,	3 00
Lassar-Cohn's Practical Urinary Analysis. (Lorenz.) ( <i>In preparation.</i> )		
Löb's Electrolysis and Electrosynthesis of Organic Compounds. (Lorenz.) .....	12mo,	1 00
Mandel's Handbook for Bio-chemical Laboratory.....	12mo,	1 50
Mason's Water-supply. (Considered Principally from a Sanitary Standpoint.).....	8vo,	5 00
“ Examination of Water. (Chemical and Bacteriological.) .....	12mo,	1 25
Meyer's Determination of Radicles in Carbon Compounds. (Tingle.) .....	12mo,	1 00
Miller's Manual of Assaying.....	12mo,	1 00
Mixter's Elementary Text-book of Chemistry.....	12mo,	1 50
Morgan's Outline of Theory of Solution and its Results... 12mo,		1 00
“ Elements of Physical Chemistry.....	12mo,	2 00
Nichols's Water-supply. (Considered mainly from a Chemical and Sanitary Standpoint, 1883.).....	8vo,	2 50
O'Brine's Laboratory Guide in Chemical Analysis.....	8vo,	2 00
O'Driscoll's Notes on the Treatment of Gold Ores.....	8vo,	2 00
Ost and Kolbeck's Text-book of Chemical Technology. (Lorenz—Bozart.) ( <i>In preparation.</i> )		

* Penfield's Notes on Determinative Mineralogy and Record of Mineral Tests.....	8vo, paper,	0 50
Pinner's Introduction to Organic Chemistry. (Austen.)....	12mo,	1 50
Poole's Calorific Power of Fuels.....	8vo,	3 00
* Reisig's Guide to Piece-dyeing.....	8vo,	25 00
Richards and Woodman's Air, Water, and Food from a Sanitary Standpoint .....	8vo,	2 00
Richards's Cost of Living as Modified by Sanitary Science.....	12mo,	1 00
"    Cost of Food, a Study in Dietaries.....	12mo,	1 00
Ricketts and Russell's Skeleton Notes upon Inorganic Chemistry. (Part I.—Non-metallic Elements.)..	8vo, morocco,	75
Ricketts and Miller's Notes on Assaying.....	8vo,	3 00
Rideal's Sewage and the Bacterial Purification of Sewage.....	8vo,	3 50
Ruddiman's Incompatibilities in Prescriptions.....	8vo,	2 00
Schimpf's Text-book of Volumetric Analysis.....	12mo,	2 50
Spencer's Handbook for Chemists of Beet-sugar Houses.....	16mo, morocco,	3 00
"    Handbook for Sugar Manufacturers and their Chemists .....	16mo, morocco,	2 00
Stockbridge's Rocks and Soils.....	8vo,	2 50
* Tillman's Elementary Lessons in Heat.....	8vo,	1 50
*    "    Descriptive General Chemistry.....	8vo,	3 00
Turneure and Russell's Public Water-supplies.....	8vo,	5 00
Van Deventer's Physical Chemistry for Beginners. (Boltwood.).....	12mo,	1 50
Walke's Lectures on Explosives.....	8vo,	4 00
Wells's Laboratory Guide in Qualitative Chemical Analysis.....	8vo,	1 50
"    Short Course in Inorganic Qualitative Chemical Analysis for Engineering Students.....	12mo,	1 50
Whipple's Microscopy of Drinking-water.....	8vo,	3 50
Wiechmann's Sugar Analysis.....	Small 8vo,	2 50
"    Lecture-notes on Theoretical Chemistry.....	12mo,	3 00
Wilson's Cyanide Processes.....	12mo,	1 50
"    Chlorination Process.....	12mo,	1 50
Wulling's Elementary Course in Inorganic Pharmaceutical and Medical Chemistry.....	12mo,	2 00

## CIVIL ENGINEERING.

### BRIDGES AND ROOFS. HYDRAULICS. MATERIALS OF ENGINEERING. RAILWAY ENGINEERING.

Baker's Engineers' Surveying Instruments.....	12mo,	3 00
Bixby's Graphical Computing Table....	Paper, 19½ x 24½ inches.	25
Davis's Elevation and Stadia Tables.....	8vo,	1 00
Folwell's Sewerage. (Designing and Maintenance.).....	8vo,	3 00
Freitag's Architectural Engineering.....	8vo,	3 50

Goodhue's Municipal Improvements.....	12mo,	1 75
Goodrich's Economic Disposal of Towns' Refuse.....	8vo,	3 50
Gore's Elements of Geodesy.....	8vo,	2 50
Hayford's Text-book of Geodetic Astronomy.....	8vo,	3 00
Howe's Retaining-walls for Earth.....	12mo,	1 25
Johnson's Theory and Practice of Surveying.....	Small 8vo,	4 00
"    Stadia and Earth-work Tables.....	8vo,	1 25
Kiersted's Sewage Disposal.....	12mo,	1 25
Mahan's Treatise on Civil Engineering. (1873.) (Wood.)..	8vo,	5 00
* Mahan's Descriptive Geometry.....	8vo,	1 50
Merriman's Elements of Precise Surveying and Geodesy....	8vo,	2 50
Merriman and Brooks's Handbook for Surveyors....	16mo, mor.,	2 00
Merriman's Elements of Sanitary Engineering.....	8vo,	2 00
Nugent's Plane Surveying. ( <i>In preparation.</i> )		
Ogden's Sewer Design.....	12mo,	2 00
Patton's Treatise on Civil Engineering.....	8vo, half leather,	7 50
Reed's Topographical Drawing and Sketching.....	4to,	5 00
Rideal's Sewage and the Bacterial Purification of Sewage..	8vo,	3 50
Siebert and Biggin's Modern Stone-cutting and Masonry..	8vo,	1 50
Smith's Manual of Topographical Drawing. (McMillan.)..	8vo,	2 50
* Trautwine's Civil Engineer's Pocket-book....	16mo, morocco,	5 00
Wait's Engineering and Architectural Jurisprudence.....	8vo,	6 00
	Sheep,	6 50
"    Law of Operations Preliminary to Construction in En-		
gineering and Architecture.....	8vo,	5 00
	Sheep,	5 50
"    Law of Contracts.....	8vo,	3 00
Warren's Stereotomy—Problems in Stone-cutting.....	8vo,	2 50
Webb's Problems in the Use and Adjustment of Engineering		
Instruments .....	16mo, morocco,	1 25
* Wheeler's Elementary Course of Civil Engineering.....	8vo,	4 00
Wilson's Topographic Surveying .....	8vo,	3 50

## BRIDGES AND ROOFS.

Boller's Practical Treatise on the Construction of Iron Highway		
Bridges .....	8vo,	2 00
* Boller's Thames River Bridge.....	4to, paper,	5 00
Burr's Course on the Stresses in Bridges and Roof Trusses,		
Arched Ribs, and Suspension Bridges.....	8vo,	3 50
Du Bois's Stresses in Framed Structures.....	Small 4to,	10 00
Foster's Treatise on Wooden Trestle Bridges.....	4to,	5 00
Fowler's Cofferdam Process for Piers.....	8vo,	2 50
Greene's Roof Trusses.....	8vo,	1 25
"    Bridge Trusses.....	8vo,	2 50
"    Arches in Wood, Iron, and Stone.....	8vo,	2 50
Howe's Treatise on Arches.....	8vo,	4 00

Johnson, Bryan and Turneure's Theory and Practice in the Designing of Modern Framed Structures.....	Small 4to,	10 00
Merriman and Jacoby's Text-book on Roofs and Bridges:		
Part I.—Stresses in Simple Trusses.....	8vo,	2 50
Part II.—Graphic Statics.....	8vo,	2 00
Part III.—Bridge Design. Fourth Ed. ( <i>In preparation.</i> ).....	8vo,	2 50
Part IV.—Higher Structures.....	8vo,	2 50
Morison's Memphis Bridge.....	4to,	10 00
Waddell's De Pontibus, a Pocket Book for Bridge Engineers.		
	16mo, mor.,	3 00
“ Specifications for Steel Bridges.....	12mo,	1 25
Wood's Treatise on the Theory of the Construction of Bridges and Roofs .....	8vo,	2 00
Wright's Designing of Draw-spans:		
Part I.—Plate-girder Draws.....	8vo,	2 50
Part II.—Riveted-truss and Pin-connected Long-span Draws.		
	8vo,	2 50
Two parts in one volume.....	8vo,	3 50

## HYDRAULICS.

Bazin's Experiments upon the Contraction of the Liquid Vein Issuing from an Orifice. (Trautwine.).....	8vo,	2 00
Bovey's Treatise on Hydraulics.....	8vo,	5 00
Church's Mechanics of Engineering.....	8vo,	6 00
Coffin's Graphical Solution of Hydraulic Problems.....	16mo, mor.,	2 50
Flather's Dynamometers, and the Measurement of Power.....	12mo,	3 00
Folwell's Water-supply Engineering.....	8vo,	4 00
Frizell's Water-power.....	8vo,	5 00
Fuertes's Water and Public Health.....	12mo,	1 50
“ Water-filtration Works.....	12mo,	2 50
Ganguillet and Kutter's General Formula for the Uniform Flow of Water in Rivers and Other Channels. (Her- ing and Trautwine.).....	8vo,	4 00
Hazen's Filtration of Public Water-supply.....	8vo,	3 00
Hazleurst's Towers and Tanks for Water-works.....	8vo,	2 50
Herschel's 115 Experiments on the Carrying Capacity of Large, Riveted, Metal Conduits.....	8vo,	2 00
Mason's Water-supply. (Considered Principally from a Sani- tary Standpoint.).....	8vo,	5 00
Merriman's Treatise on Hydraulics.....	8vo,	4 00
* Michie's Elements of Analytical Mechanics.....	8vo,	4 00
Schuyler's Reservoirs for Irrigation, Water-power, and Domestic Water-supply.....	Large 8vo,	5 00
Turneure and Russell. Public Water-supplies.....	8vo,	5 00
Wegmann's Design and Construction of Dams.....	4to,	5 00
“ Water-supply of the City of New York from 1658 to 1895 .....	4to,	10 00
Weisbach's Hydraulics and Hydraulic Motors. (Du Bois.).....	8vo,	5 00
Wilson's Manual of Irrigation Engineering.....	Small 8vo,	4 00
Wolff's Windmill as a Prime Mover.....	8vo,	3 00
Wood's Turbines.....	8vo,	2 50
“ Elements of Analytical Mechanics.....	8vo,	3 00

## MATERIALS OF ENGINEERING.

Baker's Treatise on Masonry Construction.....	8vo,	5 00
Black's United States Public Works.....	Oblong 4to,	5 00
Bovey's Strength of Materials and Theory of Structures....	8vo,	7 50



Goodhue's Munic	and Resistance of the Materials of Engineer	8vo,	5 00
Goodrich's Econ	.....	8vo,	5 00
Gore's Element	.....	16mo,	3 00
Hayford's Text	.....	8vo,	6 00
Howe's Retair	.....	Small 4to,	10 00
Johnson's The	.....	Large 8vo,	6 00
" Sta	.....	8vo,	7 50
Kiersted's S	.....	2 vols., 8vo,	7 50
Mahan's Tr	.....	8vo,	5 00
* Mahan's	.....	8vo,	4 00
Merriman	.....	12mo,	1 00
Merriman	.....	12mo,	2 00
Merriman	.....	8vo,	5 00
Nugent's	.....	12mo,	1 25
Ogden's	.....	Small 4to,	3 00
Patton	.....	12mo,	2 00
Reed's	.....	12mo,	2 00
Ridea	.....	3 Parts, 8vo,	8 00
Siebe	.....	8vo,	2 00
Smit	.....	8vo,	3 50
* Tr	.....	8vo,	2 50
Wa	.....	8vo,	5 00
	.....	8vo,	4 00
	.....	16mo, morocco,	3 00
	.....	12mo,	1 25
	.....	8vo,	2 00
	.....	8vo,	3 00

## RAILWAY ENGINEERING.

Berg's Buildings and Structures of American Railroads.	4to,	5 00
Brooks's Handbook of Street Railroad Location.	16mo, morocco,	1 50
Butts's Civil Engineer's Field-book.	16mo, morocco,	2 50
Crandall's Transition Curve.	16mo, morocco,	1 50
" Railway and Other Earthwork Tables.	8vo,	1 50
Dawson's Electric Railways and Tramways.	Small 4to, half mor.,	12 50
" "Engineering" and Electric Traction Pocket-book.	16mo, morocco,	4 00
Dredge's History of the Pennsylvania Railroad: (1879.)	Paper,	5 00
* Drinker's Tunneling, Explosive Compounds, and Rock Drills.	4to, half morocco,	25 00
Fisher's Table of Cubic Yards.	Cardboard,	25
Godwin's Railroad Engineers' Field-book and Explorers' Guide.	16mo, morocco,	2 50
Howard's Transition Curve Field-book.	16mo, morocco,	1 50
Hudson's Tables for Calculating the Cubic Contents of Excavations and Embankments.	8vo,	1 00
Nagle's Field Manual for Railroad Engineers.	16mo, morocco,	3 00
Philbrick's Field Manual for Engineers.	16mo, morocco,	3 00
Pratt and Alden's Street-railway Road-bed.	8vo,	2 00

Searles's Field Engineering.....	16mo, morocco,	3 00
“ Railroad Spiral.....	16mo, morocco,	1 50
Taylor's Prismoidal Formulæ and Earthwork.....	8vo,	1 50
* Trautwine's Method of Calculating the Cubic Contents of Ex- cavations and Embankments by the Aid of Dia- grams .....	8vo,	2 00
* “ The Field Practice of Laying Out Circular Curves for Railroads.....	12mo, morocco,	2 50
* “ Cross-section Sheet.....	Paper,	25
Webb's Railroad Construction.....	8vo,	4 00
Wellington's Economic Theory of the Location of Railways..	Small 8vo,	5 00

## DRAWING.

Barr's Kinematics of Machinery.....	8vo,	2 50
* Bartlett's Mechanical Drawing.....	8vo,	3 00
Durley's Elementary Text-book of the Kinematics of Machines. ( <i>In preparation.</i> )		
Hill's Text-book on Shades and Shadows, and Perspective.....	8vo,	2 00
Jones's Machine Design:		
Part I.—Kinematics of Machinery.....	8vo,	1 50
Part II.—Form, Strength and Proportions of Parts.....	8vo,	3 00
MacCord's Elements of Descriptive Geometry.....	8vo,	3 00
“ Kinematics; or, Practical Mechanism.....	8vo,	5 00
“ Mechanical Drawing.....	4to,	4 00
“ Velocity Diagrams.....	8vo,	1 50
* Mahan's Descriptive Geometry and Stone-cutting.....	8vo,	1 50
Mahan's Industrial Drawing. (Thompson.).....	8vo,	3 50
Reed's Topographical Drawing and Sketching.....	4to,	5 00
Reid's Course in Mechanical Drawing.....	8vo,	2 00
“ Text-book of Mechanical Drawing and Elementary Ma- chine Design.....	8vo,	3 00
Robinson's Principles of Mechanism.....	8vo,	3 00
Smith's Manual of Topographical Drawing. (McMillan.).....	8vo,	2 50
Warren's Elements of Plane and Solid Free-hand Geometrical Drawing .....	12mo,	1 00
“ Drafting Instruments and Operations.....	12mo,	1 25
“ Manual of Elementary Projection Drawing.....	12mo,	1 50
“ Manual of Elementary Problems in the Linear Per- spective of Form and Shadow.....	12mo,	1 00
“ Plane Problems in Elementary Geometry.....	12mo,	1 25
“ Primary Geometry.....	12mo,	75
“ Elements of Descriptive Geometry, Shadows, and Per- spective .....	8vo,	3 50
“ General Problems of Shades and Shadows.....	8vo,	3 00
“ Elements of Machine Construction and Drawing.....	8vo,	7 50
“ Problems, Theorems, and Examples in Descriptive Geometry .....	8vo,	2 50
Weisbach's Kinematics and the Power of Transmission. (Herr- mann and Klein.).....	8vo,	5 00
Whelpley's Practical Instruction in the Art of Letter En- graving .....	12mo,	2 00
Wilson's Topographic Surveying.....	8vo,	3 50
Wilson's Free-hand Perspective.....	8vo,	2 50
Woolf's Elementary Course in Descriptive Geometry..	Large 8vo,	3 00

## ELECTRICITY AND PHYSICS.

Anthony and Brackett's Text-book of Physics. (Magie.)	Small 8vo,	3 00
Anthony's Lecture-notes on the Theory of Electrical Measurements	12mo,	1 00
Benjamin's History of Electricity	8vo,	3 00
Benjamin's Voltaic Cell	8vo,	3 00
Classen's Quantitative Chemical Analysis by Electrolysis. Her- rick and Boltwood.)	8vo,	3 00
Crehore and Squier's Polarizing Photo-chronograph	8vo,	3 00
Dawson's Electric Railways and Tramways.	Small 4to, half mor.,	12 50
Dawson's "Engineering" and Electric Traction Pocket-book.	16mo, morocco,	4 00
Flather's Dynamometers, and the Measurement of Power	12mo,	3 00
Gilbert's De Magnete. (Mottelay.)	8vo,	2 50
Holman's Precision of Measurements	8vo,	2 00
" Telescopic Mirror-scale Method, Adjustments, and Tests	Large 8vo,	75
Landauer's Spectrum Analysis. (Tingle.)	8vo,	3 00
Le Chatelier's High-temperature Measurements. (Boudouard— Burgess.)	12mo,	3 00
Löb's Electrolysis and Electrosynthesis of Organic Compounds. (Lorenz.)	12mo,	1 00
Lyons's Treatise on Electromagnetic Phenomena	8vo,	6 00
* Michie. Elements of Wave Motion Relating to Sound and Light	8vo,	4 00
Niaudet's Elementary Treatise on Electric Batteries (Fish- back.)	12mo,	2 50
* Parshall and Hobart's Electric Generators.	Small 4to, half mor.,	10 00
Thurston's Stationary Steam-engines	8vo,	2 50
* Tillman. Elementary Lessons in Heat	8vo,	1 50
Tory and Pitcher. Manual of Laboratory Physics	Small 8vo,	2 00

## LAW.

* Davis. Elements of Law	8vo,	2 50
* " Treatise on the Military Law of United States.	8vo,	7 00
"	Sheep,	7 50
Manual for Courts-martial	16mo, morocco,	1 50
Wait's Engineering and Architectural Jurisprudence	8vo,	6 00
"	Sheep,	6 50
" Law of Operations Preliminary to Construction in En- gineering and Architecture	8vo,	5 00
"	Sheep,	5 50
" Law of Contracts	8vo,	3 00
Winthrop's Abridgment of Military Law	12mo,	2 50

## MANUFACTURES.

Beaumont's Woollen and Worsted Cloth Manufacture	12mo,	1 50
Bernadou's Smokeless Powder—Nitro-cellulose and Theory of the Cellulose Molecule	12mo,	2 50
Bolland's Iron Founder	12mo, cloth,	2 50
" "The Iron Founder" Supplement	12mo,	2 50
" Encyclopedia of Founding and Dictionary of Foundry Terms Used in the Practice of Moulding	12mo,	3 00
Eissler's Modern High Explosives	8vo,	4 00
Effront's Enzymes and their Applications. (Prescott.) ( <i>In preparation.</i> )		
Fitzgerald's Boston Machinist	18mo,	1 00

Ford's Boiler Making for Boiler Makers.....	18mo,	1 00
Hopkins's Oil-chemists' Handbook.....	8vo,	3 00
Keep's Cast Iron. ( <i>In preparation.</i> ).....		
Metcalf's Steel. A Manual for Steel-users.....	12mo,	2 00
Metcalf's Cost of Manufactures—And the Administration of Workshops, Public and Private.....	8vo,	5 00
Meyer's Modern Locomotive Construction.....	4to,	10 00
* Reising's Guide to Piece-dyeing.....	8vo,	25 00
Smith's Press-working of Metals.....	8vo,	3 00
“ Wire: Its Use and Manufacture.....	Small 4to,	3 00
Spalding's Hydraulic Cement.....	12mo,	2 00
Spencer's Handbook for Chemists of Beet-sugar Houses.....	16mo, morocco,	3 00
“ Handbook for Sugar Manufacturers and their Chem- ists.....	16mo, morocco,	2 00
Thurston's Manual of Steam-boilers, their Designs, Construc- tion and Operation.....	8vo,	5 00
Walke's Lectures on Explosives.....	8vo,	4 00
West's American Foundry Practice.....	12mo,	2 50
“ Moulder's Text-book.....	12mo,	2 50
Wiechmann's Sugar Analysis.....	Small 8vo,	2 50
Wolff's Windmill as a Prime Mover.....	8vo,	3 00
Woodbury's Fire Protection of Mills.....	8vo,	2 50

## MATHEMATICS.

Baker's Elliptic Functions.....	8vo,	1 50
* Bass's Elements of Differential Calculus.....	12mo,	4 00
Briggs's Elements of Plane Analytic Geometry.....	12mo,	1 00
Chapman's Elementary Course in Theory of Equations....	12mo,	1 50
Compton's Manual of Logarithmic Computations.....	12mo,	1 50
Davis's Introduction to the Logic of Algebra.....	8vo,	1 50
Halsted's Elements of Geometry.....	8vo,	1 75
“ Elementary Synthetic Geometry.....	8vo,	1 50
Johnson's Three-place Logarithmic Tables: Vest-pocket size, pap., 100 copies for.....		5 00
Mounted on heavy cardboard, 8 × 10 inches, 10 copies for.....		2 00
“ Elementary Treatise on the Integral Calculus. Small 8vo,		1 50
“ Curve Tracing in Cartesian Co-ordinates.....	12mo,	1 00
“ Treatise on Ordinary and Partial Differential Equations.....	Small 8vo,	3 50
“ Theory of Errors and the Method of Least Squares.....	12mo,	1 50
* “ Theoretical Mechanics.....	12mo,	3 00
* Ludlow and Bass. Elements of Trigonometry and Logarith- mic and Other Tables.....	8vo,	3 00
“ Trigonometry. Tables published separately. Each,		2 00
Merriman and Woodward. Higher Mathematics.....	8vo,	5 00
Merriman's Method of Least Squares.....	8vo,	2 00
Rice and Johnson's Elementary Treatise on the Differential Calculus.....	Small 8vo,	3 00
“ Differential and Integral Calculus. 2 vols. in one.....	Small 8vo,	2 50
Wood's Elements of Co-ordinate Geometry.....	8vo,	2 00
“ Trigonometry: Analytical, Plane, and Spherical....	12mo,	1 00

## MECHANICAL ENGINEERING. MATERIALS OF ENGINEERING, STEAM ENGINES AND BOILERS.

Baldwin's Steam Heating for Buildings.....	12mo,	2 50
Barr's Kinematics of Machinery.....	8vo,	2 50
* Bartlett's Mechanical Drawing.....	8vo,	3 00
Benjamin's Wrinkles and Recipes.....	12mo,	2 00
Carpenter's Experimental Engineering.....	8vo,	6 00
"    Heating and Ventilating Buildings.....	8vo,	3 00
Clerk's Gas and Oil Engine.....	Small 8vo,	4 00
Cromwell's Treatise on Toothed Gearing.....	12mo,	1 50
"    Treatise on Belts and Pulleys.....	12mo,	1 50
Durley's Elementary Text-book of the Kinematics of Machines.....		
(In preparation.)		
Flather's Dynamometers, and the Measurement of Power ..	12mo,	3 00
"    Rope Driving.....	12mo,	2 00
Gill's Gas an Fuel Analysis for Engineers.....	12mo,	1 25
Hall's Car Lubrication.....	12mo,	1 00
Jones's Machine Design:		
Part I.—Kinematics of Machinery.....	8vo,	1 50
Part II.—Form, Strength and Proportions of Parts.....	8vo,	3 00
Kent's Mechanical Engineers' Pocket-book....	16mo, morocco,	5 00
Kerr's Power and Power Transmission. (In preparation.)		
MacCord's Kinematics; or, Practical Mechanism.....	8vo,	5 00
"    Mechanical Drawing.....	4to,	4 00
"    Velocity Diagrams.....	8vo,	1 50
Mahan's Industrial Drawing. (Thompson.).....	8vo,	3 50
Poole's Calorific Power of Fuels.....	8vo,	3 00
Reid's Course in Mechanical Drawing.....	8vo,	2 00
"    Text-book of Mechanical Drawing and Elementary Machine Design.....	8vo,	3 00
Richards's Compressed Air.....	12mo,	1 50
Robinson's Principles of Mechanism.....	8vo,	3 00
Smith's Press-working of Metals.....	8vo,	3 00
Thurston's Treatise on Friction and Lost Work in Machin- ery and Mill Work.....	8vo,	3 00
"    Animal as a Machine and Prime Motor and the Laws of Energetics.....	12mo,	1 00
Warren's Elements of Machine Construction and Drawing.....	8vo,	7 50
Weisbach's Kinematics and the Power of Transmission. (Herr- mann—Klein.) .....	8vo,	5 00
"    Machinery of Transmission and Governors. (Herr- mann—Klein.) .....	8vo,	5 00
"    Hydraulics and Hydraulic Motors. (Du Bois.).....	8vo,	5 00
Wolff's Windmill as a Prime Mover.....	8vo,	3 00
Wood's Turbines.....	8vo,	2 50

## MATERIALS OF ENGINEERING.

Bovey's Strength of Materials and Theory of Structures.....	8vo,	7 50
Burr's Elasticity and Resistance of the Materials of Engineer- ing .....	8vo,	5 00
Church's Mechanics of Engineering.....	8vo,	6 00
Johnson's Materials of Construction.....	Large 8vo,	6 00
Keep's Cast Iron. (In preparation.)		
Lanza's Applied Mechanics.....	8vo,	7 50
Martens's Handbook on Testing Materials. (Henning.)....	8vo,	7 50
Merriman's Text-book on the Mechanics of Materials.....	8vo,	4 00
"    Strength of Materials.....	12mo,	1 00

Metcalf's Steel. A Manual for Steel-users.....	12mo,	2 00
Smith's Wire: Its Use and Manufacture.....	Small 4to,	3 00
Thurston's Materials of Engineering.....	3 vols., 8vo,	8 00
Part II.—Iron and Steel.....	8vo,	3 50
Part III.—A Treatise on Brasses, Bronzes and Other Alloys and their Constituents.....	8vo,	2 50
Thurston's Text-book of the Materials of Construction.....	8vo,	5 00
Wood's Treatise on the Resistance of Materials and an Ap- pendix on the Preservation of Timber.....	8vo,	2 00
"    Elements of Analytical Mechanics.....	8vo,	3 00

## STEAM ENGINES AND BOILERS.

Carnot's Reflections on the Motive Power of Heat. (Thurston.)	12mo,	1 50
Dawson's "Engineering" and Electric Traction Pocket-book.	16mo, morocco,	4 00
Ford's Boiler Making for Boiler Makers.....	18mo,	1 00
Hemenway's Indicator Practice and Steam-engine Economy.	12mo,	2 00
Hutton's Mechanical Engineering of Power Plants.....	8vo,	5 00
"    Heat and Heat-engines.....	8vo,	5 00
Kent's Steam-boiler Economy.....	8vo,	4 00
Kneass's Practice and Theory of the Injector.....	8vo,	1 50
MacCord's Slide-valves.....	8vo,	2 00
Meyer's Modern Locomotive Construction.....	4to,	10 00
Peabody's Manual of the Steam-engine Indicator.....	12mo,	1 50
"    Tables of the Properties of Saturated Steam and Other Vapors.....	8vo,	1 00
"    Thermodynamics of the Steam-engine and Other Heat-engines.....	8vo,	5 00
"    Valve-gears for Steam-engines.....	8vo,	2 50
Peabody and Miller. Steam-boilers.....	8vo,	4 00
Pray's Twenty Years with the Indicator.....	Large 8vo,	2 50
Pupin's Thermodynamics of Reversible Cycles in Gases and Saturated Vapors. (Osterberg.).....	12mo,	1 25
Reagan's Locomotive Mechanism and Engineering.....	12mo,	2 00
Rontgen's Principles of Thermodynamics. (Du Bois.).....	8vo,	5 00
Sinclair's Locomotive Engine Running and Management.....	12mo,	2 00
Smart's Handbook of Engineering Laboratory Practice.....	12mo,	2 50
Snow's Steam-boiler Practice.....	8vo,	3 00
Spangler's Valve-gears.....	8vo,	2 50
"    Notes on Thermodynamics.....	12mo,	1 00
Thurston's Handy Tables.....	8vo,	1 50
"    Manual of the Steam-engine.....	2 vols., 8vo,	10 00
Part I.—History, Structure, and Theory.....	8vo,	6 00
Part II.—Design, Construction, and Operation.....	8vo,	6 00
Thurston's Handbook of Engine and Boiler Trials, and the Use of the Indicator and the Prony Brake.....	8vo,	5 00
"    Stationary Steam-engines.....	8vo,	2 50
"    Steam-boiler Explosions in Theory and in Prac- tice.....	12mo,	1 50
"    Manual of Steam-boilers, Their Designs, Construc- tion, and Operation.....	8vo,	5 00
Weisbach's Heat, Steam, and Steam-engines. (Du Bois.).....	8vo,	5 00
Whitham's Steam-engine Design.....	8vo,	5 00
Wilson's Treatise on Steam-boilers. (Flather.).....	16mo,	2 50
Wood's Thermodynamics, Heat Motors, and Refrigerating Machines.....	8vo,	4 00

## MECHANICS AND MACHINERY.

Barr's Kinematics of Machinery.....	8vo,	2 50
Bovey's Strength of Materials and Theory of Structures.....	8vo,	7 50
Chordal.—Extracts from Letters.....	12mo,	2 00
Church's Mechanics of Engineering.....	8vo,	6 00
"    Notes and Examples in Mechanics.....	8vo,	2 00
Compton's First Lessons in Metal-working.....	12mo,	1 50
Compton and De Groodt. The Speed Lathe.....	12mo,	1 50
Cromwell's Treatise on Toothed Gearing.....	12mo,	1 50
"    Treatise on Belts and Pulleys.....	12mo,	1 50
Dana's Text-book of Elementary Mechanics for the Use of Colleges and Schools.....	12mo,	1 50
Dingey's Machinery Pattern Making.....	12mo,	2 00
Dredge's Record of the Transportation Exhibits Building of the World's Columbian Exposition of 1893.....	4to, half mor.,	5 00
Du Bois's Elementary Principles of Mechanics:		
Vol. I.—Kinematics.....	8vo,	3 50
Vol. II.—Statics.....	8vo,	4 00
Vol. III.—Kinetics.....	8vo,	3 50
Du Bois's Mechanics of Engineering. Vol. I.....	Small 4to,	10 00
Durley's Elementary Text-book of the Kinematics of Machines. <i>(In preparation.)</i>		
Fitzgerald's Boston Machinist.....	16mo,	1 00
Flather's Dynamometers, and the Measurement of Power.....	12mo,	3 00
"    Rope Driving.....	12mo,	2 00
Hall's Car Lubrication.....	12mo,	1 00
Holly's Art of Saw Filing.....	18mo,	75
* Johnson's Theoretical Mechanics.....	12mo,	3 00
Jones's Machine Design:		
Part I.—Kinematics of Machinery.....	8vo,	1 50
Part II.—Form, Strength and Proportions of Parts.....	8vo,	3 00
Kerr's Power and Power Transmission. <i>(In preparation.)</i>		
Lanza's Applied Mechanics.....	8vo,	7 50
MacCord's Kinematics; or, Practical Mechanism.....	8vo,	5 00
"    Velocity Diagrams.....	8vo,	1 50
Merriman's Text-book on the Mechanics of Materials.....	8vo,	4 00
* Michie's Elements of Analytical Mechanics.....	8vo,	4 00
Reagan's Locomotive Mechanism and Engineering.....	12mo,	2 00
Reid's Course in Mechanical Drawing.....	8vo,	2 00
"    Text-book of Mechanical Drawing and Elementary Machine Design.....	8vo,	3 00
Richards's Compressed Air.....	12mo,	1 50
Robinson's Principles of Mechanism.....	8vo,	3 00
Sinclair's Locomotive-engine Running and Management.....	12mo,	2 00
Smith's Press-working of Metals.....	8vo,	3 00
Thurston's Treatise on Friction and Lost Work in Machinery and Mill Work.....	8vo,	3 00
"    Animal as a Machine and Prime Motor, and the Laws of Energetics.....	12mo,	1 00
Warren's Elements of Machine Construction and Drawing.....	8vo,	7 50
Weisbach's Kinematics and the Power of Transmission. <i>(Herrman—Klein.)</i> .....	8vo,	5 00
"    Machinery of Transmission and Governors. <i>(Herr-</i> <i>man—Klein.)</i> .....	8vo,	5 00
Wood's Elements of Analytical Mechanics.....	8vo,	3 00
"    Principles of Elementary Mechanics.....	12mo,	1 25
"    Turbines.....	8vo,	2 50
The World's Columbian Exposition of 1893.....	4to,	1 00

## METALLURGY.

Egleston's Metallurgy of Silver, Gold, and Mercury:	
Vol. I.—Silver.....	8vo, 7 50
Vol. II.—Gold and Mercury.....	8vo, 7 50
Keep's Cast Iron. ( <i>In preparation.</i> )	
Kunhardt's Practice of Ore Dressing in Europe.....	8vo, 1 50
Le Chatelier's High-temperature Measurements. (Boudouard—Burgess.) .....	12mo, 3 00
Metcalf's Steel. A Manual for Steel-users.....	12mo, 2 00
Thurston's Materials of Engineering. In Three Parts.....	8vo, 8 00
Part II.—Iron and Steel.....	8vo, 3 50
Part III.—A Treatise on Brasses, Bronzes and Other Alloys and Their Constituents.....	8vo, 2 50

## MINERALOGY.

Barringer's Description of Minerals of Commercial Value.	
Oblong, morocco,	2 50
Boyd's Resources of Southwest Virginia.....	8vo, 3 00
" Map of Southwest Virginia.....	Pocket-book form, 2 00
Brush's Manual of Determinative Mineralogy. (Penfield.)	8vo, 4 00
Chester's Catalogue of Minerals.....	8vo, paper, 1 00
	Cloth, 1 25
" Dictionary of the Names of Minerals.....	8vo, 3 50
Dana's System of Mineralogy.....	Large 8vo, half leather, 12 50
" First Appendix to Dana's New "System of Mineralogy."	
	Large 8vo, 1 00
" Text-book of Mineralogy.....	8vo, 4 00
" Minerals and How to Study Them.....	12mo, 1 50
" Catalogue of American Localities of Minerals.	Large 8vo, 1 00
" Manual of Mineralogy and Petrography.....	12mo, 2 00
Egleston's Catalogue of Minerals and Synonyms.....	8vo, 2 50
Hussak's The Determination of Rock-forming Minerals. (Smith.) .....	Small 8vo, 2 00
* Penfield's Notes on Determinative Mineralogy and Record of Mineral Tests.....	8vo, paper, 50
Rosenbusch's Microscopical Physiography of the Rock-making Minerals. (Idding's.) .....	8vo, 5 00
* Tillman's Text-book of Important Minerals and Rocks.	8vo, 2 00
Williams's Manual of Lithology.....	8vo, 3 00

## MINING.

Beard's Ventilation of Mines.....	12mo, 2 50
Boyd's Resources of Southwest Virginia.....	8vo, 3 00
" Map of Southwest Virginia.....	Pocket-book form, 2 00
* Drinker's Tunneling, Explosive Compounds, and Rock Drills.....	4to, half morocco, 25 00
Eissler's Modern High Explosives.....	8vo, 4 00
Goodyear's Coal-mines of the Western Coast of the United States .....	12mo, 2 50
Ihlseng's Manual of Mining.....	8vo, 4 00
Kunhardt's Practice of Ore Dressing in Europe.....	8vo, 1 50
O'Driscoll's Notes on the Treatment of Gold Ores.....	8vo, 2 00
Sawyer's Accidents in Mines.....	8vo, 7 00
Walke's Lectures on Explosives.....	8vo, 4 00
Wilson's Cyanide Processes.....	12mo, 1 50
Wilson's Chlorination Process.....	12mo, 1 50



Wilson's Hydraulic and Placer Mining.....	12mo,	2 00
Wilson's Treatise on Practical and Theoretical Mine Ventilation .....	12mo,	1 25

### SANITARY SCIENCE.

Folwell's Sewerage. (Designing, Construction and Maintenance.)	8vo,	3 00
“ Water-supply Engineering.....	8vo,	4 00
Fuertes's Water and Public Health.....	12mo,	1 50
“ Water-filtration Works.....	12mo,	2 50
Gerhard's Guide to Sanitary House-inspection.....	16mo,	1 00
Goodrich's Economical Disposal of Towns' Refuse...Demy	8vo,	3 50
Hazen's Filtration of Public Water-supplies.....	8vo,	3 00
Kiersted's Sewage Disposal.....	12mo,	1 25
Mason's Water-supply. (Considered Principally from a Sanitary Standpoint.....	8vo,	5 00
“ Examination of Water. (Chemical and Bacteriological.) .....	12mo,	1 25
Merriman's Elements of Sanitary Engineering.....	8vo,	2 00
Nichols's Water-supply. (Considered Mainly from a Chemical and Sanitary Standpoint.) (1883.) .....	8vo,	2 50
Ogden's Sewer Design.....	12mo,	2 00
Richards's Cost of Food. A Study in Dietaries.....	12mo,	1 00
Richards and Woodman's Air, Water, and Food from a Sanitary Standpoint.....	8vo,	2 00
Richards's Cost of Living as Modified by Sanitary Science.....	12mo,	1 00
Rideal's Sewage and Bacterial Purification of Sewage.....	8vo,	3 50
Turneaure and Russell's Public Water-supplies.....	8vo,	5 00
Whipple's Microscopy of Drinking-water.....	8vo,	3 50
Woodhull's Notes on Military Hygiene.....	16mo,	1 50

### MISCELLANEOUS.

Barker's Deep-sea Soundings.....	8vo,	2 00
Emmons's Geological Guide-book of the Rocky Mountain Excursion of the International Congress of Geologists.	Large 8vo,	1 50
Ferrel's Popular Treatise on the Winds.....	8vo,	4 00
Haines's American Railway Management.....	12mo,	2 50
Mott's Composition, Digestibility, and Nutritive Value of Food.	Mounted chart,	1 25
“ Fallacy of the Present Theory of Sound.....	16mo,	1 00
Ricketts's History of Rensselaer Polytechnic Institute, 1824-1894.....	Small 8vo,	3 00
Rotherham's Emphasised New Testament.....	Large 8vo,	2 00
“ Critical Emphasised New Testament.....	12mo,	1 50
Steel's Treatise on the Diseases of the Dog.....	12mo,	3 50
Totten's Important Question in Metrology.....	8vo,	2 50
The World's Columbian Exposition of 1893.....	4to,	1 00
Worcester and Atkinson. Small Hospitals, Establishment and Maintenance, and Suggestions for Hospital Architecture, with Plans for a Small Hospital.....	12mo,	1 25

### HEBREW AND CHALDEE TEXT-BOOKS.

Green's Grammar of the Hebrew Language.....	8vo,	3 00
“ Elementary Hebrew Grammar.....	12mo,	1 25
“ Hebrew Chrestomathy.....	8vo,	2 00
Gesenius's Hebrew and Chaldee Lexicon to the Old Testament Scriptures. (Tregelles.).....	Small 4to, half morocco,	5 00
Letteris's Hebrew Bible.....	8vo,	2 25









LIBRARY  
GRADUATE SCHOOL OF ENGINEERING  
HARVARD UNIVERSITY

Please sign your name and address  
on this card, and deposit in box  
provided.

This book may be kept

**ONE WEEK**

HARVARD ENGINEERING SCHOOL